

PIPE UNDERDRAIN SCHEDULE - MAINLINE

LANE	STATION TO STATION	PIPE UNDERDRAINS 6" (FOOT)	PIPE UNDERDRAINS (SPECIAL) 6" (FOOT)	CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	SHOULDER REMOVAL AND REPLACEMENT 12" (FOOT)	REMARKS
SB LT	1212+00 1217+00	500	13	1		PLUG STA. 1212+00, OUTLET STA. 1217+00
SB RT	1212+00 1217+00	500	18	1	500	PLUG STA. 1212+00, OUTLET STA. 1217+00
NB LT	1217+00 1221+00	400	18	1		PLUG STA. 1217+00, OUTLET STA. 1221+00
NB RT	1217+00 1221+00	400	13	1	400	PLUG STA. 1217+00, OUTLET STA. 1221+00
SB LT	1217+00 1221+00	400	13	1		PLUG STA. 1217+00, OUTLET STA. 1221+00
SB RT	1217+00 1221+00	400	18	1	400	PLUG STA. 1217+00, OUTLET STA. 1221+00
NB LT	1221+00 1225+00	400	18	1		PLUG STA. 1221+00, OUTLET STA. 1225+00
NB RT	1221+00 1225+00	400	18		400	PLUG STA. 1221+00, MEDIAN INLET STA. 1225+00
SB LT	1221+00 1225+00	400	18			PLUG STA. 1221+00, MEDIAN INLET STA. 1225+00
SB RT	1221+00 1225+00	400	18	1	400	PLUG STA. 1221+00, OUTLET STA. 1225+00
NB LT	1225+00 1230+20	520	18	1		PLUG STA. 1225+00, OUTLET STA. 1230+25
NB RT	1225+00 1230+20	520	18		520	PLUG STA. 1225+00, MEDIAN INLET STA. 1230+25
SB LT	1225+00 1230+20	520	18			PLUG STA. 1225+00, MEDIAN INLET STA. 1230+25
SB RT	1225+00 1230+20	520	18	1	520	PLUG STA. 1225+00, OUTLET STA. 1230+25
NB LT	1230+20 1235+00	480	18			OUTLET STA. 1230+25, PLUG STA. 1235+00
NB RT	1230+20 1235+00	480	18		480	MEDIAN INLET STA. 1230+25, PLUG STA. 1235+00
SB LT	1230+20 1235+00	480	18			MEDIAN INLET STA. 1230+25, PLUG STA. 1235+00
SB RT	1230+20 1235+00	480	18		480	OUTLET STA. 1230+25, PLUG STA. 1235+00
NB LT	1235+00 1240+00	500	18	1		OUTLET STA. 1235+00, PLUG STA. 1240+00
NB RT	1235+00 1240+00	500	18		500	MEDIAN INLET STA. 1235+00, PLUG STA. 1240+00
SB LT	1235+00 1240+00	500	18			MEDIAN INLET STA. 1235+00, PLUG STA. 1240+00
SB RT	1235+00 1240+00	500	18	1	500	OUTLET STA. 1235+00, PLUG STA. 1240+00
NB LT	1240+00 1244+90	490	18	1		OUTLET STA. 1240+00, PLUG STA. 1244+90
NB RT	1240+00 1244+50	450	13	1	450	OUTLET STA. 1240+00, PLUG STA. 1244+50
SB LT	1240+00 1244+50	450	13	1		OUTLET STA. 1240+00, PLUG STA. 1244+50
SB RT	1240+00 1244+50	400	18	1	400	OUTLET STA. 1240+00, PLUG STA. 1244+50
SB RT	1244+00 1249+00	500	18	1	500	OUTLET STA. 1244+00, PLUG STA. 1249+00
NB RT	1244+50 1249+00	450	18		450	MEDIAN INLET STA. 1244+50, PLUG STA. 1249+00
SB LT	1244+50 1249+00	450	18			MEDIAN INLET STA. 1244+50, PLUG STA. 1249+00
NB LT	1244+90 1249+00	410	18	1		OUTLET STA. 1244+90, PLUG STA. 1249+00
NB RT	1249+00 1251+00	200	18	1		PLUG STA. 1249+00, OUTLET STA. 1251+00
NB RT	1249+00 1250+65	165	18		165	PLUG STA. 1249+00, MEDIAN INLET STA. 1250+65
SB LT	1249+00 1250+65	165	18			PLUG STA. 1249+00, MEDIAN INLET STA. 1250+65
SB RT	1249+00 1250+35	135	18	1	135	PLUG STA. 1249+00, OUTLET STA. 1250+35
SB RT	1250+35 1259+20	885	18	1	885	PLUG STA. 1250+35, OUTLET STA. 1259+20
NB RT	1250+65 1258+50	785	18		785	PLUG STA. 1250+65, MEDIAN INLET STA. 1258+50
SB LT	1250+65 1258+50	785	18			PLUG STA. 1250+65, MEDIAN INLET STA. 1258+50
NB LT	1251+00 1260+00	900	18	1		PLUG STA. 1251+00, OUTLET STA. 1260+00
NB RT	1259+50 1263+75	425	18		425	MEDIAN INLET STA. 1259+50, PLUG STA. 1263+75
SB LT	1259+50 1263+00	350	18			MEDIAN INLET STA. 1259+50, PLUG STA. 1263+00
SB RT	1259+20 1261+65	245	18		245	OUTLET STA. 1259+20, PLUG STA. 1261+65
NB LT	1260+00 1263+75	375	18			OUTLET STA. 1260+00, TIE IN STA. 1263+75
TOTALS =		227,725	7,936	347	110,610	

PIPE UNDERDRAIN SCHEDULE - IL 140

LANE	STATION TO STATION	PIPE UNDERDRAINS 6" (FOOT)	PIPE UNDERDRAINS (SPECIAL) 6" (FOOT)	CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	SHOULDER REMOVAL AND REPLACEMENT 8" (FOOT)	SHOULDER REMOVAL AND REPLACEMENT 12" (FOOT)	REMARKS
RAMP 1 LT	100+50 105+00	450	20	1	450		PLUG STA. 100+50, OUTLET STA. 105+00
RAMP 1 RT	100+50 105+00	450	20	1	450		PLUG STA. 100+50, OUTLET STA. 105+00
RAMP 1 LT	105+00 107+50	250	20	1	250		PLUG STA. 105+00, OUTLET STA. 107+50
RAMP 1 RT	105+00 108+50	350	20	1	350		PLUG STA. 105+00, OUTLET STA. 108+50
RAMP 1 RT	108+50 110+00	150	20			150	OUTLET STA. 108+50, PLUG STA. 110+00
RAMP 1 RT	110+00 112+65	265	18			265	PLUG STA. 110+00, OUTLET STA. 112+65
RAMP 2 RT	200+75 203+00	225	18			225	OUTLET STA. 200+75, PLUG STA. 203+00
RAMP 2 RT	203+00 209+00	600	20	1	200	400	PLUG STA. 203+00, OUTLET STA. 208+00
RAMP 2 LT	206+00 209+00	300	20	1	300		PLUG STA. 206+00, OUTLET STA. 209+00
RAMP 2 LT	209+00 213+50	450	20		450		OUTLET STA. 209+00, PLUG STA. 213+50
RAMP 2 RT	209+00 213+00	400	20		400		OUTLET STA. 209+00, PLUG STA. 213+00
RAMP 2 RT	213+00 218+00	500	20	1	500		OUTLET STA. 213+00, PLUG STA. 218+00
RAMP 2 LT	213+50 218+00	450	20	1	450		OUTLET STA. 213+50, PLUG STA. 218+00
RAMP 3 LT	300+50 303+10	260	20	1	260		PLUG STA. 300+50, OUTLET STA. 303+10
RAMP 3 RT	300+50 305+50	500	20	1	500		PLUG STA. 300+50, OUTLET STA. 305+50
RAMP 3 LT	303+10 307+00	390	20	1	390		PLUG STA. 303+10, OUTLET STA. 307+00
RAMP 3 RT	305+50 308+50	300	20	1	300		PLUG STA. 305+50, OUTLET STA. 308+50
RAMP 3 LT	307+00 308+00	100	20		100		OUTLET STA. 307+00, PLUG STA. 308+00
RAMP 3 RT	308+50 310+50	200	20			400	OUTLET STA. 308+50, PLUG STA. 310+50
RAMP 3 RT	310+50 315+50	500	20	1		400	PLUG STA. 310+50, OUTLET STA. 315+50
RAMP 4 RT	400+50 404+00	350	20			400	OUTLET STA. 400+50, PLUG STA. 404+00
RAMP 4 RT	404+00 408+00	400	20	1	200	200	PLUG STA. 404+00, OUTLET STA. 408+00
RAMP 4 LT	406+00 408+00	200	20		200		PLUG STA. 406+00, OUTLET STA. 408+00
RAMP 4 LT	408+00 411+00	300	20		300		OUTLET STA. 408+00, PLUG STA. 411+00
RAMP 4 RT	408+00 414+00	600	20		600		OUTLET STA. 408+00, PLUG STA. 414+00
RAMP 4 LT	411+00 416+00	500	20	1	500		OUTLET STA. 411+00, PLUG STA. 416+00
RAMP 4 RT	414+00 418+50	450	20	1	450		OUTLET STA. 414+00, PLUG STA. 418+50
RAMP 4 LT	416+00 418+50	250	20	1	250		OUTLET STA. 416+00, PLUG STA. 418+50
TOTALS =		10,140	556	18	7,850	2,440	

PIPE UNDERDRAIN SCHEDULE - REST AREA

LANE	STATION TO STATION	PIPE UNDERDRAINS 6" (FOOT)	PIPE UNDERDRAINS (SPECIAL) 6" (FOOT)	CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	SHOULDER REMOVAL AND REPLACEMENT 8" (FOOT)	SHOULDER REMOVAL AND REPLACEMENT 12" (FOOT)	REMARKS
SB RT	99+00 105+00	600	20	1	250	350	PLUG STA. 99+00, OUTLET STA. 105+00
SB RT	105+00 110+40	540	20	1	540		PLUG STA. 105+00, OUTLET STA. 110+40
SB LT	106+60 110+40	380	20	1	380		PLUG STA. 106+60, OUTLET STA. 110+40
SB LT	110+40 112+50	210	20		210		OUTLET STA. 110+40, PLUG STA. 112+50
SB RT	110+40 112+50	210	20		210		OUTLET STA. 110+40, PLUG STA. 112+50
SB LT	132+00 135+00	300	20	1	300		PLUG STA. 132+00, OUTLET STA. 135+00
SB RT	132+00 134+00	200	20	1	200		PLUG STA. 132+00, OUTLET STA. 134+00
SB RT	134+00 139+00	500	20	1	200	300	PLUG STA. 134+00, OUTLET STA. 139+00
SB RT	139+00 142+50	350	20	1		350	PLUG STA. 139+00, OUTLET STA. 142+50
SB RT	142+50 146+50	400	20			400	OUTLET STA. 142+50, PLUG STA. 146+50
SB RT	146+50 154+20	770	20	1		770	OUTLET STA. 146+50, PLUG STA. 154+20
							NOTE: SB ENTRANCE RAMP STA. 154+20 = I-55 SB RT STA. 840+00
NB RT	101+00 105+80	480	20	1		480	PLUG STA. 101+00, OUTLET STA. 105+80
NB RT	105+80 111+50	570	20	1	490	80	PLUG STA. 105+80, OUTLET STA. 111+50
NB LT	106+60 111+60	500	20	1	500		PLUG STA. 106+60, OUTLET STA. 111+60
NB LT	133+00 139+00	600	20	1	400	200	OUTLET STA. 133+00, PLUG STA. 139+00
NB RT	133+00 136+00	300	20	1	300		OUTLET STA. 133+00, PLUG STA. 136+00
NB RT	136+00 140+90	490	20	1		490	OUTLET STA. 136+00, PLUG STA. 140+90
TOTALS =		7,400	340	14	3,980	3,420	

FILE NAME = ...oaddd\0876C93-sht-schedule.dgn
 USER NAME = SJS
 DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

PLLOT SCALE = 50.0000 ' / IN.
 PLLOT DATE = 06/23/2010 15:32:18
 REVISIONS
 REVISIONS
 REVISIONS
 REVISIONS

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. R.T.E. 55 SECTION 60-1,2,RS-2 COUNTY MADISON TOTAL SHEETS 156 SHEET NO. 26 CONTRACT NO. 76C93 ILLINOIS FED. AID PROJECT