


SUMMARY OF QUANTITIES

Code No.	Item	CONSTRUCTION TYPE CODE Y003	
		Units	Quantity
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	45
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	38
20800150	TRENCH BACKFILL	CU YD	70
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1666
* 25000100	SEEDING, CLASS 1	ACRE	0.5
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45
* 25100115	MULCH, METHOD 2	ACRE	0.5
* 25100630	EROSION CONTROL BLANKET	SQ YD	94
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50
28000500	INLET AND PIPE PROTECTION	EACH	11
28000400	PERIMETER EROSION BARRIER	FOOT	998
* 28000720	MULCH, METHOD 2	ACRE	0.5
28100107	STONE RIPRAP, CLASS A4	SQ YD	46
28200200	FILTER FABRIC	SQ YD	46
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1037
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1645
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	308
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8256
42400800	DETECTABLE WARNINGS	SQ FT	216
44000100	PAVEMENT REMOVAL	SQ YD	1230
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	383
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1278
44000600	SIDEWALK REMOVAL	SQ FT	288
50901760	PIPE HANDRAIL	FOOT	30
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	236
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	154

* SPECIALTY ITEM



SHIVE HATTERY
 Cedar Rapids, IA • Iowa City, IA • Des Moines, IA
 Moline, IL • Bloomington, IL • Chicago, IL
 SHIVE-HATTERY, INC. 1701 RIVER DRIVE, SUITE 200 MOLINE, IL 61265
 PHONE (309) 764-7650 FAX (309) 764-8616
 http://www.shive-hattery.com
 ILLINOIS FIRM NUMBER: 184-000214

Code No.	Item	CONSTRUCTION TYPE CODE Y003	
		Units	Quantity
55100500	STORM SEWER REMOVAL 12"	FOOT	246
55100700	STORM SEWER REMOVAL 15"	FOOT	167
60218400	MANHOLE TYPE A, 4 FOOT DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	885
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1375
63200310	GUARDRAIL REMOVAL	FOOT	300
67100100	MOBILIZATION	LS	1
70101700	TRAFFIC CONTROL AND PROTECTION	LS	1
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	500
Z0003850	BENCHES	EACH	4
Z0007430	TEMPORARY SIDEWALK	SQ FT	1470
Z0013798	CONSTRUCTION LAYOUT	LS	1
* Z0020000	ELECTRICAL SYSTEM COMPLETE	LS	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LS	1
* A2000324	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	12
* A2004824	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	9
* B2000668	TREE, AMELANCHIER X GRANDIFLORA (APPLE SERVICE BERRY), 7' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	3
* B2006268	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 7' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	5
* C2C09918	SHRUB, SPIREA X BUMALDA GOLDFLAME (GOLD FLAME BUMALD SPIREA), 18" HEIGHT, CONTAINER	EACH	40
* C2C11024	SHRUB, SYRINGA PATULA MISS KIM (MISS KIM MANCHURIAN LILAC), 2' HEIGHT, CONTAINER	EACH	3
* C2C15761	SHRUB, SPIREA JAPONICA NEON FLASH (NEON FLASH JAPANESE SPIREA), 18" HEIGHT, 5-GALLON CONTAINER	EACH	10
* K012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	3
LR420129	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL) WITH INTEGRAL CURB	SQ YD	312
X0323443	PRECAST MODULAR RETAINING WALL	SQ FT	225
* X2110100	TOPSOIL FURNISH AND PLACE, SPECIAL	CU YD	103
XX006868	PORTLAND CEMENT CONCRETE PAVEMENT, TEXTURED AND COLORED, 8"	SQ YD	305