

**PAVEMENT MARKING SCHEDULE**

LOCATION		THERMOPLASTIC PAVEMENT MARKING - LINE 4"		POLYUREA PAVEMENT MARKING - LINE 4"		POLYUREA PAVEMENT MARKING - LINE 8"	POLYUREA PAVEMENT MARKING - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
STATION TO STATION	SIDE	SOLID WHITE (FOOT)	DOUBLE YELLOW (FOOT)	SOLID WHITE (FOOT)	DOUBLE YELLOW (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	(EACH)	(EACH)
ILLINOIS ROUTE 1									
748+00.00 TO 756+09.99	LT	606.7							
748+00.00 TO 755+97.99	CENTER		1596.0					9	
748+00.00 TO 755+85.99	RT	786.0							
755+85.99 TO 759+85.33	RT			399.3					
755+97.99 TO 759+97.33	CENTER				798.7				5
756+09.99 TO 760+09.33	LT			399.3					
759+85.33 TO 770+00.00	RT	1014.7							
759+97.33 TO 770+00.00	CENTER		2005.3					13	
760+09.33 TO 770+00.00	LT	990.7							
EMPIRE STREET									
4+12.93 TO 5+23.36				452.5	218.9	61.6	30.0	1	
SUBTOTAL		3398.1	3601.3	1251.1	1017.6	61.6	30.0	23	5
TOTAL		7000		2269		62	30	23	5

**GUARDRAIL SCHEDULE**

LOCATION		TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT	STEEL PLATE BEAM GUARD RAIL TYPE A	TRAFFIC BARRIER TERMINAL TYPE 6	GUARDRAIL REMOVAL	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
STATION TO STATION	SIDE	(EACH)	(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)
752+50.25 TO 755+94.00	RT	1	250	1		4	1
752+53.28 TO 756+34.53	LT	1	287.5	1		4	1
754+19.86 TO 760+78.94	RT				658.7		
755+15.09 TO 761+73.85	LT				658.77		
759+60.79 TO 762+04.54	RT	1	150	1		4	1
760+01.32 TO 763+45.07	LT	1	250	1		4	1
TOTAL		4	937.5	4	1317.47	16	4
PAY TOTAL		4	937.5	4	1318	16	4

**EROSION CONTROL SCHEDULE**

LOCATION		EARTH EXCAVATION FOR EROSION CONTROL (CU YD)	TEMPORARY DITCH CHECKS (EACH)	PERIMETER EROSION BARRIER (FOOT)	INLET AND PIPE PROTECTION (EACH)	AGGREGATE (EROSION CONTROL) (TON)	TEMPORARY EROSION CONTROL SEEDING (POUNDS)
STATION	SIDE	(CU YD)	(EACH)	(FOOT)	(EACH)	(TON)	(POUNDS)
ILLINOIS ROUTE 1							
748+00 TO 757+50	LT/RT						398
749+70.61 TO 750+30.56	LT			113			
749+71.00	LT				1		
750+36	LT	2.37				0.57	
751+03.00	RT	2.37				0.57	
751+10.00 TO 757+23.56	RT			646			
751+80.00	LT		1				
752+18.00	LT		1				
752+56.00	LT		1				
752+95.00	LT		1				
753+33.00	LT		1				
753+50.00 TO 757+23.56	LT			468			
754+08.00	LT		1				
754+83.00	LT		1				
755+58.00	LT		1				
756+43.00	LT	2.37				0.57	
757+53.00	LT				1		
758+50 TO 770+00.00	LT/RT						446
758+78.57 TO 764+91.94	RT			724			
758+78.57 TO 767+37.72	LT			896			
765+02.70 TO 767+09.99	RT			253			
767+21.50 TO 768+22.33	RT			104			
767+62.28 TO 768+46.49	LT			86			
768+39.21 TO 770+00.00	RT			164			
768+82.04 TO 770+00.00	LT			116			
EMPIRE STREET							
4+36.67 TO 5+50.00	LT/RT						12
TOTAL		7.11	8	3570	2	1.71	856
PAY TOTAL		8	8	3570	2	2	860

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION (CU YD)	FOR INFORMATION ONLY			FURNISHED EXCAVATION (CU YD)	POROUS GRANULAR BACKFILL, SPECIAL (TON)	REMARKS
		EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25% (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)			
748+00.00 TO 757+20.00	765	615	18900	-18285	18285		
758+75.00 TO 770+00.00	795	640	29560	-28920	28920	3982	
EMPIRE	140	110	90	20	-20		
TOTAL		1700	1365	48550	47185	3982	

**SURVEY MARKERS SCHEDULE**

LOCATION		PERMANENT SURVEY MARKERS, TYPE 1 (EACH)
STATION	OFFSET	(EACH)
754+53.58	0.00	1
760+10.00	0.00	1
763+97.80	0.00	1
TOTAL		3

**SEEDING SCHEDULE**

LOCATION		SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)
ILLINOIS ROUTE 1						
748+00.00 TO 757+50.00		1.99	179	179	179	1.99
758+50.00 TO 770+00.00		2.23	201	201	201	2.23
EMPIRE STREET						
4+36.67 TO 5+50.00		0.06	6	6	6	0.06
TOTAL		4.28	386	386	386	4.28
PAY TOTAL		4.5	405	405	405	4.5