

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	TOTAL
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24
20100500	TREE REMOVAL, ACRES	ACRE	2.0
20200100	EARTH EXCAVATION	CJ YD	11295
20400800	FURNISHED EXCAVATION	CJ YD	5640
25000305	SEEDING, CLASS 3A	ACRE	2.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180
25100115	MULCH, METHOD 2	ACRE	0.5
25100630	EROSION CONTROL BLANKET	SQ YD	6078
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400
28000305	TEMPORARY DITCH CHECKS	FOOT	204
28000400	PERIMETER EROSION BARRIER	FOOT	2513
28000500	INLET AND PIPE PROTECTION	EACH	9
28100107	STONE RIPRAP, CLASS A4	SQ YD	702
28200200	FILTER FABRIC	SQ YD	702
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	4961
35101400	AGGREGATE BASE COURSE, TYPE B	TON	10
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	23
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	4
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	4093
42001300	PROTECTIVE COAT	SQ YD	5064
44000100	PAVEMENT REMOVAL	SQ YD	311
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	432
44004250	PAVED SHOULDER REMOVAL	SQ YD	278
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	81
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CJ YD	1365
50300225	CONCRETE STRUCTURES	CJ YD	179.8
50300280	CONCRETE ENCASEMENT	CJ YD	18.2
50800105	REINFORCEMENT BARS	POUND	14305
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2885
X5091725	BICYCLE RAILING, SPECIAL	FOOT	72
51201600	FURNISHING STEEL PILES HP12x53	FOOT	1775
51202305	DRIVING PILES	FOOT	1775
51203600	TEST PILE STEEL HP12x53	EACH	2
51500100	NAME PLATES	EACH	1
54201105	PIPE CULVERTS, CLASS D, TYPE 2 60"	FOOT	264
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7

CODE NO.	ITEM	UNITS	TOTAL
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	294
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	8
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	7
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2751.0
64100115	SIGHT SCREEN (WOODEN FENCE), TYPE P 6'	FOOT	145
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	132
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4382
78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	236
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	35
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	66
X0321156	HIGH VISIBILITY TEMPORARY FENCING	FOOT	1251
X0008399	THREE SIDED PRECAST CONCRETE STRUCTURES 36"x12'	FOOT	60

• SPECIALTY ITEM

HURST-ROSCHKE ENGINEERS, INC.
 HILLSBORO, ILLINOIS 62049
 (217)532-3959 FAX (217)532-3212



FILE NAME =	USER NAME = #USER#	DESIGNED - JJC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - UJ	REVISED -					05-00002-00-RP	CHAMPAIGN	35	3
PLOT SCALE = #SCALE#		CHECKED - MAR	REVISED -					CONTRACT NO. 99425			
PLOT DATE = #DATE#		DATE -	REVISED -					FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT			

...dgn\S00.dgn 7/14/2010 2:44:22 PM