

PAVEMENT MARKING AND GUARDRAIL SCHEDULE

LOCATION	63000003		63100085		63100167		63301210		63301990		78001110			Z0001002	
	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS		TRAFFIC BARRIER TERMINAL, TYPE 6		TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A		REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1		PAINT PAVEMENT MARKING - LINE 4"			GUARDRAIL AGGREGATE EROSION CONTROL	
	(FOOT)		(EACH)		(EACH)		(FOOT)		(EACH)		(FOOT)			(TON)	
	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	CL	RT	LT	RT
ILLINOIS 251															
766+00.00 - 766+50.00								23.52		1					
766+50.00 - 767+00.00								50.00							
767+00.00 - 767+50.00								50.00							
767+50.00 - 768+00.00								50.00							
768+00.00 - 768+50.00								50.00							
768+50.00 - 769+00.00								50.00							4.5
769+00.00 - 769+50.00				36.02				14.00							4.5
769+50.00 - 770+00.00				50.00											4.5
770+00.00 - 770+50.00				50.00							50.00	100.00	50.00		4.5
770+50.00 - 771+00.00				50.00							50.00	100.00	50.00		4.5
771+00.00 - 771+50.00				50.00							50.00	100.00	50.00		4.5
771+50.00 - 772+00.00	23.50	50.00									50.00	100.00	50.00	2.1	4.5
772+00.00 - 772+50.00	50.00	50.00			1.00						50.00	100.00	50.00	4.5	4.5
772+50.00 - 773+00.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
773+00.00 - 773+50.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
773+50.00 - 774+00.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
774+00.00 - 774+50.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
774+50.00 - 775+00.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
775+00.00 - 775+50.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
775+50.00 - 776+00.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
776+00.00 - 776+50.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
776+50.00 - 777+00.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
777+00.00 - 777+50.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
777+50.00 - 778+00.00	14.00	14.00	1.00	1.00							50.00	100.00	50.00	1.3	1.3
778+00.00 - 778+50.00											50.00	100.00	50.00		
BRIDGE OMISSION															
780+00.00 - 780+50.00											150.00	300.00	150.00		
780+50.00 - 781+00.00			1.00	1.00							50.00	100.00	50.00		
781+00.00 - 781+50.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
781+50.00 - 782+00.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
782+00.00 - 782+50.00	50.00	50.00									50.00	100.00	50.00	4.5	4.5
782+50.00 - 783+00.00															
783+00.00 - 783+50.00															
783+50.00 - 784+00.00															
784+00.00 - 784+50.00															
GOOD NEIGHBOR															
											14280.00	28560.00	14280.00		
TOTAL	737.50	1000.02	2	2	1	0	0	287.5	0	1	15530	31060	15530	66.40	95.80
ADJUSTED TOTAL	1738		4		1		288		1		62120			163	

2

REVISED 2 9/03/21 JMM

FILE NAME = Z:\2010\160240_PTB1811\cadd\Civil\Dgn\W03-4\SHNDZ09616-rl-schedule_05.dgn

WBK ENGINEERING, LLC
 116 WEST MAIN STREET, SUITE 201
 ST. CHARLES, ILLINOIS 60174
 (630) 443-7755

USER NAME = jmuller	DESIGNED - KAC	REVISED - 2 9/03/2021 JMM
PLOT SCALE = 1:2	DRAWN - VLM	REVISED -
PLOT DATE = 9/3/2021	CHECKED - YOO	REVISED -
	DATE - 6/23/21	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES IL 251 OVER 500 LINE RAILROAD			
SCALE:	SHEET 5	OF 9 SHEETS	STA. TO STA.

FAS RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1042	106VBR-D	OGLE	107	19
CONTRACT NO. 64L75				
ILLINOIS FED. AID PROJECT				