

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	KEDZIE AVE. BRIDGE SFTY-2A
20200100	EARTH EXCAVATION	CU YD	163	163
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	37	37
28100209	STONE RIPRAP, CLASS A5	TON	80	80
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	488	488
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	178	178
42001166	BRIDGE APPROACH PAVEMENT	SQ YD	386	386
42001200	PAVEMENT FABRIC	SQ YD	178	178
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	108	108
44000100	PAVEMENT REMOVAL	SQ YD	178	178
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	228	228
44000702	APPROACH SLAB REMOVAL, SPECIAL	SQ YD	431	431
44003100	MEDIAN REMOVAL	SQ FT	2,595	2,595
50102400	CONCRETE REMOVAL	CU YD	89.5	89.5
50157300	PROTECTIVE SHIELD	SQ YD	750	750
50200100	STRUCTURE EXCAVATION	CU YD	37	37
50300225	CONCRETE STRUCTURES	CU YD	30.2	30.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	185.9	185.9
50300260	BRIDGE DECK GROOVING	SQ YD	1,772	1,772
50300300	PROTECTIVE COAT	SQ YD	2,395	2,395
50300530	FLOOR DRAIN EXTENSION	EACH	66	66
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4,990	4,990
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	27	27
50501130	STRUCTURAL STEEL REPAIR	POUND	1,300	1,300
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	65,710	65,710
50800515	BAR SPLICERS	EACH	522	522
52000110	PREFORMED JOINT STRIP SEAL	FOOT	171	171
52000216	FINGER PLATE EXPANSION JOINT, 5"	FOOT	56	56

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	KEDZIE AVE. BRIDGE SFTY-2A
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	67	67
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10	10
52100520	ANCHOR BOLTS, 1"	EACH	54	54
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	108	108
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	1,800	1,800
60624600	CORRUGATED MEDIAN	SQ FT	567	567
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION,(SPECIAL)	L SUM	1	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	40	40
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3,384	3,384
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	34	34
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20	20
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	20	20
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	100	100
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1,864	1,864
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	554	554
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	7,227	7,227
X0712400	TEMPORARY PAVEMENT	SQ YD	250	250
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	10	10
XX006752	REMOVE, STORE AND RE-INSTALL EXISTING MONUMENT	L SUM	1	1
Z0006198	BRIDGE DECK HYDRO-SCARIFICATION 1/4"	SQ YD	1,864	1,864
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5	5
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	89	89
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	5	5
78300100	PAVEMENT MARKING REMOVAL	SQ FT	528	528

* SPECIALTY ITEM