

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000	X080-2A	CODE NO.	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000	X080-2A
20200100	EARTH EXCAVATION	CU YD	220	220		44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	60	60	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	1611	1611		44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	75	75	
25000310	SEEDING, CLASS 4	ACRE	0.3	0.3		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1815	1815	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27		50102400	CONCRETE REMOVAL	CU YD	11		11
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27		50300225	CONCRETE STRUCTURES	CU YD	53		53
25100630	EROSION CONTROL BLANKET	SQ YD	1611	1611		50300255	CONCRETE SUPERSTRUCTURE	CU YD	272		272
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30	30		50300260	BRIDGE DECK GROOVING	SQ YD	524		524
28000300	TEMPORARY DITCH CHECKS	EACH	2	2		50300300	PROTECTIVE COAT	SQ YD	1201		1201
28000400	PERIMETER EROSION BARRIER	FOOT	1089	1089		50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	4894		4894
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	49		49	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	72,930		72,930
35600704	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	SQ YD	248	248		50800515	BAR SPLICERS	EACH	291		291
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3		51500100	NAME PLATES	EACH	1		1
40600300	AGGREGATE (PRIME COAT)	TON	11	11		52000110	PREFORMED JOINT STRIP SEAL	FOOT	87		87
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	4	4		59000200	EPOXY CRACK INJECTION	FOOT	161		161
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	102	102		* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	46	46		* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	4	4	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	28	28		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	160	160		67100100	MOBILIZATION	L SUM	1	1	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	54	54		70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431	EACH	1	1	
44000100	PAVEMENT REMOVAL	SQ YD	221	221		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2219	2219		70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
44000700	APPROACH SLAB REMOVAL	SQ YD	107		107	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	150	150	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	165	165		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	669	669	
44004250	PAVED SHOULDER REMOVAL	SQ YD	369	369		70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	1324	1324	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	30	30		70400100	TEMPORARY CONCRETE BARRIER	FOOT	300	300	

*Specialty Items

* SPECIALTY ITEMS

LOWCO, INC.
CONSULTING ENGINEERS
1560 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY
DRAWN - ST
CHECKED - MJY
DATE - 07/08/2009

REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL ROUTE 58 (GOLF ROAD)**

SCALE: NONE SHEET NO. 3 OF 33 SHEETS STA. 492+55 TO STA. 498+45

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1320	581 B-1	COOK	33	3
D-91-288-09			CONTRACT NO. 60F91	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev