

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	<i>LIBRAN</i> TOTAL	1000	X080-2A	CODE NO.	ITEM	UNIT	TOTAL	1000	X080-2A
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	300	300							
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1202	1202							
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	263	263							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	24	24							
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4							
* 78200500	BARRIER WALL MARKERS	EACH	26	26							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16							
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52							
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	6515	6515							
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	544		544						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12							
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	58		58						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2							
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2							
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1							

* SPECIALTY ITEMS

LONCO, INC.
CONSULTING ENGINEERS
1960 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST	REVISED -
CHECKED - MJY	REVISED -
DATE - 07/08/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL ROUTE 58 (GOLF ROAD)**

SCALE: NONE SHEET NO. 4 OF 31 SHEETS STA. 492+55 TO STA. 498+45

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1320	581 B-1	COOK	33	4
D-91-288-09		CONTRACT NO. 60F91		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		