

DATE	
BY	
REVIEWED	
PLOTTED	
TEMPLATE	
AREAS	
CHECKED	
FINAL SURVEY	
NOTE BOOK	
NO.	

DATE	
BY	
REVIEWED	
PLOTTED	
TEMPLATE	
AREAS	
CHECKED	
ORIGINAL SURVEY	
NOTE BOOK	
NO.	

SUMMARY OF QUANTITIES			URBAN 801.FED. 201.STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000- URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	42	42
40600300	AGGREGATE (PRIME COAT)	TON	204	204
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	986	986
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	492	492
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5,002	5,002
42001300	PROTECTIVE COAT	SQ YD	3,145	3,145
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	800	800
42400800	DETECTABLE WARNINGS	SQ FT	8	8
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	51,041	51,041
44000600	SIDEWALK REMOVAL	SQ FT	800	800
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5,157	5,157
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,930	2,930
44003100	MEDIAN REMOVAL	SQ FT	12,034	12,034
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	100	100
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2,300	2,300
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	200	200
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	330	330
44213100	PAVEMENT FABRIC	SQ YD	1,337	1,337
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1,600	1,600
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	28	28
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	69	69
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2
60624610	CORRUGATED MEDIAN (DOWELLED)	SQ FT	12,034	12,034
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14,000	14,000

SUMMARY OF QUANTITIES			URBAN 801.FED. 201.STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000- URBAN
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	416	416
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20,000	20,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,072	2,072
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	209	209
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	168	168
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,000	3,000
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	416	416
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,000	20,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,072	2,072
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	209	209
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	168	168
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	747	747
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	459	459
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,060	1,060
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	50	50
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,144	2,144
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	76	76
⊙ Z0076600	TRAINEES	HOURL	500	500

⊙ V080  
NP = Non-participating  
\* SPECIALTY ITEM

FILE NAME = D168F39-shv-S00.dgn  
PLOT DATE = 6/26/2009



DESIGNED -	M.P.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	G.F.L.	REVISED -	
DATE -	JUNE 2009	REVISED -	

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
WAUKEGAN ROAD (MILWAUKEE AVE TO DEMPSTER ST)

SCALE: NONE SHEET NO. OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	3271 A-RS-3	COOK	29	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				CONTRACT NO. 60H56