



SECTION A-A

NOTES:
 1) STAGGER LEFT DOWEL BAR 18" FROM RIGHT DOWEL BAR AND PLACE BOTH AT 3'-0" INTERVALS OR AS DIRECTED BY THE ENGINEER.
 2) THE COST OF FURNISHING AND INSTALLING DOWEL BARS AND MORTAR FILLING SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER SQ. FT. FOR CORRUGATED MEDIAN (DOWELLED).

- LEGEND**
- EXISTING INLET
 - EXISTING CATCH BASIN
 - ⊙ EXISTING MANHOLE
 - E ELECTRIC
 - W WATER
 - CE COM ED (ADJUSTMENTS PERFORMED BY OTHERS)
 - T TELEPHONE (ADJUSTMENTS PERFORMED BY OTHERS)
 - G GAS
 - ⊕ SP FRAMES AND LIDS TO BE ADJUSTED, SPECIAL
 - DRAINAGE STRUCTURES TO BE CLEANED
 - ADJ FRAMES AND LIDS TO BE ADJUSTED
 - REC DRAINAGE STRUCTURES TO BE RECONSTRUCTED

DATE	
BY	
SURVEYED	
PLOTTED	
TEMP. DATE	
NOTE BOOK	
AREAS CHECKED	
NO.	

DATE	
BY	
ORIGINAL SURVEY	
PLOTTED	
TEMP. DATE	
NOTE BOOK	
AREAS CHECKED	
NO.	

CR CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - M.P.	REVISED -
DRAWN - B.K.	REVISED -
CHECKED - G.F.L.	REVISED -
DATE - JUNE 2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY PLAN
WAUKEGAN ROAD (MILWAUKEE AVE TO DEMPSTER ST)
 SCALE: 1" = 50' SHEET NO. 2 OF 4 SHEETS STA. 35+00 TO STA. 65+00

F.A.P. RTE. 348	SECTION 3271 A-RS-3	COUNTY COOK	TOTAL SHEETS 29	SHEET NO. 6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 60H56