SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	263	263					
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	20	20					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1					
* 25100630	EROSION CONTROL BLANKET	SQ YD	20	20					
* 25200110	SODDING, SALT TOLERANT	SQ YD	20	20					
* 25200200	SUPPLEMENTAL WATERING	UNIT	1	1					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1	1					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	86	86					
40600300	AGGREGATE (PRIME COAT)	TON	410	410					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	154	154					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	148	148					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	611	611					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8846	8846					
42001300	PROTECTIVE COAT	SQ YD	1865	1865					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	102246	102246					
44000300	CURB REMOVAL	FOOT	70	70					
44000400	GUTTER REMOVAL	FOOT	70	70					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5420	5420					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	428	428					
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	4843	4843					
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	100	100					
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	130	130					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	790	790					
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	480	480					
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	2080	2080					
44201774	CLASS D PATCHES, TYPE I, 11 1/4 INCH	SQ YD	6	6					
X4420777	CLASS D PATCHES, TYPE II, 11 1/4 INCH	SQ YD	700	700					
X4420781	CLASS D PATCHES, TYPE III, 11 1/4 INCH	SQ YD	360	360					
X4420783	CLASS D PATCHES, TYPE IV, 11 1/4 INCH	SQ YD	962	962					
X4420784	CLASS D PATCHES, TYPE IV, 12 3/4 INCH	SQ YD	85	85					

* SPECIALTY ITEMS

\# NON-SPECIALTY ITEMS

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A					
44213200	SAW CUTS	FOOT	285	285					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	568	568					
Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	9	9					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2					
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3					
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	12	12					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	40	40					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	428	428					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	18	18					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15165	15165					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	372	372					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	80382	80382					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	695	695					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2030	2030					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1731	1731					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	411	411					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	36475	36475					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	372	372					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	80382	80382					

* SPECIALTY ITEMS
Δ - NON-PARTICIPATING

* FAP 856/FAU 318

Rev.

FILE NAME = c:\pw_work\PWIDOT\GALBANNEB\d0140162\D175909-sht plan.dgn	USER NAME = galbanneb	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 6/26/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 6 (CHANNAHON RD/RAILROAD ST)
SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	1-D-1-RS-3	WILL	34	3
		CONTRACT NO. 60H61		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT