

INDEX OF SHEETS

STATE STANDARDS

GENERAL NOTES

<u>SHEET NO.</u>	<u>DESCRIPTION</u>	<u>STANDARD NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET	000001-05	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS
2	INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES	442201-03	CLASS C AND D PATCHES
3	SUMMARY OF QUANTITIES	604001-03	FRAME AND LIDS, TYPE 1
4-5	EXISTING AND PROPOSED TYPICAL SECTIONS	604086-02	FRAME AND GRATE, TYPE 23
6-9	ROADWAY AND PAVEMENT MARKING PLANS	604091-02	FRAME AND GRATE, TYPE 24
10-15	DETECTOR LOOP REPLACEMENT PLANS	606001-04	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
16	DETAILS FOR FRAME AND LIDS ADJUSTMENT WITH MILLING	701426-03	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS
17	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT	701602-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
18	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT	701606-06	URBAN LANE CLOSURE, MULTILANE 2W WITH MOUNTABLE MEDIAN
19	BUTT JOINT AND HMA TAPER	701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
20	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS	701901-01	TRAFFIC CONTROL DEVICES
21	TYPICAL APPLICATIONS: RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)	886001-01	DETECTOR LOOP INSTALLATION
22	DISTRICT ONE TYPICAL PAVEMENT MARKINGS	886006-01	TYPICAL LAYOUT FOR DETECTION LOOPS
23	TRAFFIC CONTROL AND PROTECTION OF TURN BAYS (TO REMAIN OPEN TO TRAFFIC)		
24	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING		
25	ARTERIAL INFORMATION SIGNING		
26	DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN		
27	DISTRICT 1 DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING		

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT) IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS UNLESS OTHERWISE SPECIFIED.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC, THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1 1/2 INCHES WHERE THE SPEED LIMIT IS 45 MPH OR LESS, AND 1 INCH WHERE THE SPEED LIMIT IS OVER 45 MPH. WITH WRITTEN APPROVAL FROM THE RESIDENT ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM OF 1:3 (V:H).

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN IN THE PLANS.

THE RESIDENT ENGINEER SHALL CONTACT MR. DON CHIARUGI, AREA TRAFFIC FIELD ENGINEER, AT (847) 741-9857 A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF FINAL PAVEMENT MARKINGS.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE INSTALLATION OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF NAPERVILLE.

FILE NAME =	USER NAME = smthkl	DESIGNED -	REVISED - 8/5/09 K.S.	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 34 (OGDEN AVE.) EXISTING AND PROPOSED TYPICAL SECTIONS	Rev. Sheet 8-26-09			
or\pe_work\pavdo\smthkl\0142804\0176279-shit-plan.dgn	DRAWN -	REVISED -	F.A.P. RTE.			SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLDT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -	311			652 (X & X-1) RS-5	DUPAGE	27	2
PLDT DATE = 8/4/2009	DATE -	REVISED -	CONTRACT NO. 60H64				ILLINOIS FED. AID PROJECT		
				SCALE:		SHEET NO. OF SHEETS STA. TO STA.			