

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	85	85					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	43615	43615				
21400100	GRADING AND SHAPING DITCHES	FOOT	945	945					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4630	4630				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	62	62					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	470	470				
40600300	AGGREGATE (PRIME COAT)	TON	309	309					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1680	1680				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	39	39					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	650	650				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5650	5650				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	370	370					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	830	830				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7560	7560					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	43615	43615				
42001300	PROTECTIVE COAT	SO YD	10	10					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4630	4630				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	77110	77110					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	470	470				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	400					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1680	1680				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	355	355					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	650	650				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	160	160					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1060	1060				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	900	900					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1010	1010				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	170	170					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4287	4287				
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3040	3040				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	52	52				
60260100	INLETS TO BE ADJUSTED	EACH	5	5					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
60262700	INLETS TO BE RECONSTRUCTED	EACH	5	5					© 20070600	TRAINEES	HOUR	500	500				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15	15													
60404940	FRAMES AND GRATES, TYPE 23	EACH	6	6													
60404950	FRAMES AND GRATES, TYPE 24	EACH	10	10													
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													
△ 70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16950	16950													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	830	830													

Rev. B-26-09