

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29	29					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1950	1950					
40600300	AGGREGATE (PRIME COAT)	TON	144	144					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1450	1450					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22	22					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	990	990					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	900	900					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	990	990					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2772	2772					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6205	6205					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
42001300	PROTECTIVE COAT	SQ YD	335	335					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2908	2908					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	71703	71703					NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	30	30					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1500	1500					@ 20076600	TRAINEES	HOUR	500	500					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1500	1500														
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	430	430														
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	210	210														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	75	75														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13600	13600														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	485	485														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30000	30000														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2700	2700														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1950	1950														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1450	1450														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1515	1515														
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	485	485														
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30000	30000														
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2700	2700														

* SPECIALTY ITEMS
NP= Non-participating