



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 1, 2009

SUBJECT: FAU Route 1319
Project ESP-1319 (001)
Section 2009-067 RS
Cook County
Contract No. 60H73
Item No. 9, September 18, 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 64 to the Special Provisions.
4. Revised sheets 1 - 4 & 6 - 9 of the Plans.
5. Added sheet 12A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Bill Frey; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60H73

State Job # - C-91-781-09
 PPS NBR - 1-76759-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2009-067RS

Project Number
 ESP-1319/001/

Route
 FAU 1319

* REVISED : SEPTEMBER 1, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322256	TEMP INFO SIGNING	SQ FT	154.200				
* X4067107	POL LB MM IL4.75 N50	TON	1,445.000				
* Z0018500	DRAINAGE STR CLEANED	EACH	8.000				
* 20201006	GRADING & SHAP SHLDS	UNIT	92.000				
* 40600200	BIT MATLS PR CT	TON	30.000				
* 40600300	AGG PR CT	TON	149.000				
* 40600400	MIX CR JTS FLANGEWYS	TON	56.000				
40600895	CONSTRUC TEST STRIP	EACH	1.000				
* 40600982	HMA SURF REM BUTT JT	SQ YD	415.000				
* 40601005	HMA REPL OVER PATCH	TON	416.000				
* 40603340	HMA SC "D" N70	TON	3,117.000				
42001300	PROTECTIVE COAT	SQ YD	42.000				
* 44000157	HMA SURF REM 2	SQ YD	36,684.000				
* 44001700	COMB C C&G REM & REPL	FOOT	275.000				
* 44002212	HMA RM OV PATCH 3	SQ YD	2,469.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60H73

State Job # - C-91-781-09
 PPS NBR - 1-76759-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2009-067RS

Project Number
 ESP-1319/001/

Route
 FAU 1319

* REVISED : SEPTEMBER 1, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* 44201749	CL D PATCH T1 9	SQ YD	741.000				
* 44201753	CL D PATCH T2 9	SQ YD	987.000				
* 44201757	CL D PATCH T3 9	SQ YD	741.000				
* 48102100	AGG WEDGE SHLD TYPE B	TON	389.000				
* 55039700	SS CLEANED	FOOT	100.000				
60300305	FR & LIDS ADJUST	EACH	15.000				
60300310	FR & LIDS ADJUST SPL	EACH	19.000				
67000400	ENGR FIELD OFFICE A	CAL MO	3.000				
67100100	MOBILIZATION	L SUM	1.000				
70102620	TR CONT & PROT 701501	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
* 70300100	SHORT-TERM PAVT MKING	FOOT	6,696.000				
* 70300210	TEMP PVT MK LTR & SYM	SQ FT	521.000				
* 70300220	TEMP PVT MK LINE 4	FOOT	29,743.000				
* 70300240	TEMP PVT MK LINE 6	FOOT	1,680.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60H73

State Job # - C-91-781-09
 PPS NBR - 1-76759-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2009-067RS

Project Number
 ESP-1319/001/

Route
 FAU 1319

* REVISED : SEPTEMBER 1, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300260	TEMP PVT MK LINE 12	FOOT	350.000				
70300280	TEMP PVT MK LINE 24	FOOT	200.000				
* 78000100	THPL PVT MK LTR & SYM	SQ FT	521.000				
* 78000200	THPL PVT MK LINE 4	FOOT	29,743.000				
* 78000400	THPL PVT MK LINE 6	FOOT	1,680.000				
78000600	THPL PVT MK LINE 12	FOOT	350.000				
78000650	THPL PVT MK LINE 24	FOOT	200.000				
* 78100100	RAISED REFL PAVT MKR	EACH	152.000				
* 78300200	RAISED REF PVT MK REM	EACH	115.000				
* 88600600	DET LOOP REPL	FOOT	1,089.000				

PAYROLLS AND PAYROLL RECORDS (BDE) 57
PERSONAL PROTECTIVE EQUIPMENT (BDE) 59
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 59
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 60
THERMOPLASTIC PAVEMENT MARKINGS (BDE) 60
WORKING DAYS (BDE) 61
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 61
CLEANING EXISTING DRAINAGE STRUCTURES 64

Revised 06/01/2009

CLEANING EXISTING DRAINAGE STRUCTURES

Effective: September 30, 1985

Revised: January 1, 2007

All existing storm sewers, pipe culverts, manholes, catch basins and inlets shall be considered as drainage structures insofar as the interpretation of this Special Provision is concerned. When specified for payment, the location of drainage structures to be cleaned will be shown on the plans.

All existing drainage structures which are to be adjusted or reconstructed shall be cleaned in accordance with Article 602.15. This work will be paid for in accordance with Article 602.16.

All other existing drainage structures which are specified to be cleaned on the plans will be cleaned according to Article 602.15.

Basis of Payment. This work will be paid for at the contract unit price each for DRAINAGE STRUCTURES TO BE CLEANED, and at the contract unit price per foot (meter) for STORM SEWERS TO BE CLEANED.

Added 06/01/2009