

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000					
20200100	EARTH EXCAVATION	CU YD	21	21					70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	176	176					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3912	3912					
35501300	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	44	44					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	462	462					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46246	46246					
40600300	AGGREGATE (PRIME COAT)	TON	10	10					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1553	1553					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	6					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	205	205					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1056	1056					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	349	349					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	357	357					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	3027	3027					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1304	1304					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5	5					78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	462	462					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4770	4770					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46246	46246					
42001300	PROTECTIVE COAT	SQ YD	132	132					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1553	1553					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	34	34					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	205	205					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	109	109					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1056	1056					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1956	1956					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	357	357					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	54828	54828					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	868	868					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	44	44					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	276	276					
44000600	SIDEWALK REMOVAL	SQ FT	109	109					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	342	342					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	384	384					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52					
44002232	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 8"	SQ YD	6755	6755					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2159	2159					
44201015	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	1000	1000					XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	10	10					
44201019	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	700	700					NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	25					
44201021	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	500	500					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	610	610														
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	123	123														
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500														
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	16	16														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	40	40														
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	400	400														
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8														
63200310	GUARDRAIL REMOVAL	FOOT	800	800														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3														
67100100	MOBILIZATION	L SUM	1	1														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														

NP= NON-PARTICIPATING
*Specialty Items

Rev. 8-31-09

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 176 (IL 21 TO ST. MARY'S ROAD)
SUMMARY OF QUANTITIES

FILE NAME =	USER NAME = bauerd	DESIGNED -	REVISED -	SCALE: NONE	SHEET NO. 4 OF	SHEETS	STA.	TO STA.	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\p\1007\BAUERD\1043145\102204-sfr-p\ndgn	PLOT SCALE = 50,0000' / IN.	DRAWN -	REVISED -						1238	(0, 144 & 144x) RS-4	LAKE	25	3
PLOT DATE = 6/29/2009	DATE -	CHECKED -	REVISED -						CONTRACT NO. 62661				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT													

Rev.