

X	CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y007	Y031-1F	Y030-1E	Y060
					ROADWAY	CULVERT	TRAFFIC SIGNALS	LIGHTING	WATERMAIN
					80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL
X	87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 15 FT.	EACH	2			2		
X	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	3			3		
X	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 18 FT.	EACH	1			1		
X	87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1			1		
X	87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1			1		
X	87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1			1		
X	87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1			1		
X	87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1			1		
X	87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1			1		
X	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	36			36		
X	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4		
X	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15			15		
X	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	75			75		
X	88030020	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	3			3		
X	88030050	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4			4		
X	88030070	SIGNAL HEAD, L.E.D., 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2			2		
X	88030080	SIGNAL HEAD, L.E.D., 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	5			5		
X	88030110	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3			3		
X	88030210	SIGNAL HEAD, L.E.D., 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1		
X	88030250	SIGNAL HEAD, L.E.D., 2-FACE, 1-4 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	3			3		
X	88102717	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8			8		
X	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12			12		
X	88500100	INDUCTIVE LOOP DETECTOR	EACH	22			22		
X	88600100	DETECTOR LOOP, TYPE I	FOOT	1773			1715	58	
X	88700200	LIGHT DETECTOR	EACH	5			5		
X	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1		
X	88800100	PEDESTRIAN PUSH-BUTTON	EACH	8			8		
X	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1		
X	89502200	MODIFY EXISTING CONTROLLER	EACH	1			1		
X	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	12168				12168	
X	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1		
X	89502380	REMOVE EXISTING HANDHOLE	EACH	10			8	2	
X	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8			8		

X INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME =	DESIGNED <i>BLG/KRK</i>	REVISED -
		DRAWN <i>BLG/KRK</i>	REVISED -
		CHECKED <i>DJK</i>	REVISED -
		DATE <i>5-29-09</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES
ESSINGTON ROAD AT HENNEPIN DRIVE AND MALL LOOP DRIVE

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0326	06-00130-00-CH	WILL	116	9
FED. ROAD DIST. NO. 7 ILLINOIS			CONTRACT NO. 63185	
			FED. AID PROJECT M-8003(654)	

SCALE: SHEET NO. 6 OF 8 SHEETS

REV. 9-4-09