

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1,792
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	476
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	476
20800150	TRENCH BACKFILL	CU YD	94
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,292
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12,073
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	50
25000110	SEEDING, CLASS 1A	ACRE	1.3
25000314	SEEDING, CLASS 4B	ACRE	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	187
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	187
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	187
25100630	EROSION CONTROL BLANKET	SQ YD	6,531
25200100	SODDING	SQ YD	5,542
25200200	SUPPLEMENTAL WATERING	UNIT	83
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	135
28000300	TEMPORARY DITCH CHECKS	EACH	15
28000510	INLET FILTERS	EACH	38
28100105	STONE RIPRAP, CLASS A3	SQ YD	92
28200200	FILTER FABRIC	SQ YD	92
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	61
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	81
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	46
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,017
40600300	AGGREGATE (PRIME COAT)	TON	41
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	20
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	840
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	3
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3,620
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	16
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	989
42001300	PROTECTIVE COAT	SQ YD	1,089
42400800	DETECTABLE WARNINGS	SQ FT	64
44000100	PAVEMENT REMOVAL	SQ YD	768
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	7,399
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,482
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SQ YD	25
44002600	GUTTER OUTLET REMOVAL	FOOT	30
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	100
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	150
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	150
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	400

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6,357
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	11
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	23
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	656
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	158
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	18
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	2
60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	6
60214700	RESTRICTED DEPTH CATCH BASINS, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	4
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	5
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	2
60250200	CATCH BASINS TO BE ADJUSTED	EACH	10
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4,901
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	8
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	43
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	90
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,757
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	492
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	380
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	8,757
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	492
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	380
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	27
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	38
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	3,773
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	3,773
* X8950200	REBUILD EXISTING HANDHOLE	EACH	1
XX004801	BITUMINOUS BIKE PATH REMOVAL	SQ YD	61
XX004878	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	L SUM	1
XX005462	CHANGEABLE MESSAGE SIGN	WEEK	8
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3,415
Z0019600	DUST CONTROL WATERING	UNIT	5
Z0076600	TRAINEES	HOURS	500
△ XX007063	RESTRICTED DEPTH INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	2

△ Y080

\* DENOTES SPECIALTY ITEM