



F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1680	05-00038-00-PV	KANE/KENDALL	130	4
STA.		TO STA.		
FED. ROAD DIST. NO. ...		ILLINOIS	FED. AID PROJECT	

PLAN	SURVEYED	DATE
NOTE BOOK NO.	PLOTTED	
	CHECKED	
	BY	
	DATE	

PROFILE	SURVEYED	DATE
NOTE BOOK NO.	PLOTTED	
	CHECKED	
	BY	
	DATE	

SPECIALTY ITEM	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY		80% FEDERAL, 20% VILLAGE		
				1000-28		Y002 - TRAFFIC SIGNS	Y003 - LANDSCAPING	Y031 - TRAFFIC SIGNALS
	20200100	EARTH EXCAVATION	CU YD	4,963.0	4,963.0			
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	838.0	838.0			
	20800150	TRENCH BACKFILL	CU YD	780.0	780.0			
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,965.0	1,965.0			
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,400.0	3,400.0			
*	25000110	SEEDING, CLASS 1A	ACRE	2.0	2.0			
*	25000210	SEEDING, CLASS 2A	ACRE	0.7	0.7			
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	247.0	247.0			
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	247.0	247.0			
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	247.0	247.0			
*	25100125	MULCH, METHOD 3	ACRE	2.7	2.7			
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,080.0	1,080.0			
	28000300	TEMPORARY DITCH CHECKS	EACH	10.0	10.0			
	28000400	PERIMETER EROSION BARRIER	FOOT	5,063.0	5,063.0			
	28000510	INLET FILTERS	EACH	42.0	42.0			
	28100105	STONE RIPRAP, CLASS A3	SQ YD	190.0	190.0			
	35501311	HOT-MIX ASPHALT BASE COURSE, 6 3/4"	SQ YD	1,475.0	1,475.0			
	35501314	HOT-MIX ASPHALT BASE COURSE, 7 1/2"	SQ YD	710.0	710.0			
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	800.0	800.0			
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,475.0	6,475.0			
	40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	247.0	247.0			
	40600300	AGGREGATE (PRIME COAT)	TON	41.0	41.0			
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,053.0	1,053.0			
	40600895	CONSTRUCTING TEST STRIP	EACH	4.0	4.0			
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,645.0	1,645.0			
	40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	602.0	602.0			
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	144.0	144.0			
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,257.0	1,257.0			
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	297.0	297.0			
	40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	5,173.0	5,173.0			
	44000100	PAVEMENT REMOVAL	SQ YD	1,098.0	1,098.0			
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5,731.0	5,731.0			
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	942.0	942.0			
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	352.0	352.0			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	203.0	203.0			
	44004250	PAVED SHOULDER REMOVAL	SQ YD	1,337.0	1,337.0			
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	22.0	22.0			
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	55.0	55.0			
	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	297.0	297.0			
	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	200.0	200.0			
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3,985.0	3,985.0			
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	689.0	689.0			
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	10.0	10.0			
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1.0	1.0			
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1.0	1.0			
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,950.0	1,950.0			
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	175.0	175.0			
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	20.0	20.0			
	550B2520	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 2 12"	FOOT	83.0	83.0			
	55100500	STORM SEWER REMOVAL 12"	FOOT	94.0	94.0			
	60107600	PIPE UNDERDRAINS 4"	FOOT	844.0	844.0			
	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	18.0	18.0			
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	18.0	18.0			
	60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	12.0	12.0			
	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	4.0	4.0			
	60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	1.0	1.0			
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5,251.0	5,251.0			
	67100100	MOBILIZATION	L SUM	1.0	1.0			
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	1.0			
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3.0	3.0			
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,330.0	3,330.0			
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291.2	291.2			
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12,224.5	12,224.5			
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,371.0	1,371.0			
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	191.0	191.0			
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	226.0	226.0			
	70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	7,000.0	7,000.0			
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,111.0	1,111.0			
	72000100	SIGN PANEL - TYPE 1	SQ FT	125.0	125.0	89.0		36.0
	60213300	CATCH BASINS, SPECIAL	EACH	2	2			
	60218400	MANHOLES, TYPE A, 4'-DIA TYLER CL	EACH	2	2			
	60219000	MANHOLES, TYPE A, 4'-DIA, TY BFR GRATE	EACH	3	3			
	60224300	INLETS, TYPE A, TYPE B GRATE (3' DEPTH)	EACH	2	2			

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<h1>SUMMARY OF QUANTITIES</h1>	
SCALE:		DRAWN BY: KKP	
DATE: 03-26-09		CHECKED BY: TVW	