CONTRACT NO. 63207

Engineering Enterprises, Inc.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1680	05-00038-00-PV	KANE/KENDALL	130	17
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

SIGN SCHEDULE

LOCATION	R1-1-30 NUMBER REQUIRED	R1-1-30 AREA, SF	R1-2-36 NUMBER REQUIRED	R1-2-36 AREA, SF	R2-1-2430 NUMBER REQUIRED	R2-1-2430 AREA, SF	R3-5R-3036 NUMBER REQUIRED	R3-5R-3036 AREA, SF	R3-7R-30 NUMBER REQUIRED	R3-7R-30 AREA, SF	R3-17a-1230 NUMBER REQUIRED	R3-17a-1230 AREA, SF	W1-7-2448 NUMBER REQUIRED	W1-7-2448 AREA, SF	W1-8L-1824 NUMBER REQUIRED	W1-8L-1824 AREA, SF	TELESCOPING STEEL SIGN SUPPORT, LF
BASELINE ROAD																	
1999+78 RT													1	8.00			15
2000+41 LT	1	6.25															15
2002+00 RT					1	5.00											15
2010+00 LT					1	5.00											
2011+90 RT													1	8.00			15
2012+45 LT															1	3.00	15
2012+85 LT															1	3.00	15
2013+25 LT															1	3.00	15
2013+65 LT															1	3.00	15
2014+05 LT															1	3.00	15
2014+45 LT															1	3.00	15
BASELINE EXTENSION																	
2051+58			1	3.90													15
2052+00	1	6.25															15
HORSEMEN TRAIL																	
18+75 LT									1	6.25							15
ORCHARD ROAD																	
84+93.75 RT							1	7.50									15
CATERPILLAR DRIVE																	
3004+50 LT									1	6.25							15
3007+25 LT									1	6.25	1	2.50					15
TOTAL	**2**	**12.50**	**1**	**3.90**	**2**	**10.00**	**1**	**7.50**	**3**	**18.75**	**1**	**2.50**	**2**	**16.00**	**6**	**18.00**	**240**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGN SCHEDULE

SCALE:

DATE: 03-26-09

DRAWN BY: KKP

CHECKED BY: TVW

PLAN: SURVEYED / PLOTTED / ALIGNMENT CHECKED / TC & PVI ADDED / CADD FILE NAME / NOTE BOOK NO. / BY / DATE

PROFILE: SURVEYED / PLOTTED / GRADES CHECKED / BLM VERIF. / STRUCTURE NOTATNS CHKD / NOTE BOOK NO. / BY / DATE

Plotted: June 26, 2009 @ 8:48 AM By: Kris Pung - Tab: 17 Sign Schedule 22x34

Path: H:\SIGNPROJ\M00755\DWG\DWG FINAL ENG\M00755-SCHEDULE