

SPECIAL PROVISION	PAY ITEM NUMBER	DESCRIPTION	UNIT	QUANTITY
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2,348
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	519
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	656
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	484
•	55039700	STORM SEWERS TO BE CLEANED	FOOT	100
•	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	5
	56400800	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	3
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	1.8
	60107800	PIPE UNDERDRAINS 8"	FOOT	143
•	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	10
•	60201340	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 24 FRAME AND GRATE	EACH	25
•	60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	6
•	60203905	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
•	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1
	60206705	CATCH BASINS, TYPE B	EACH	1
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	3
	60218400	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
	60221100	MANHOLES, TYPE A, 5' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
	60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	22
	60255500	MANHOLES TO BE ADJUSTED	EACH	1
•	60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	3
	60260100	INLETS TO BE ADJUSTED	EACH	2
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
	60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	6
•	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	9
	60500060	REMOVING INLETS	EACH	22
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,516
•	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	9,241
	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	694
	60619200	CONCRETE MEDIAN, TYPE SB-6.06	SO FT	2,110
	60624600	CORRUGATED MEDIAN	SO FT	282
•	61140200	STORM SEWERS, SPECIAL 12"	FOOT	106
▲	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	590
	63200310	GUARDRAIL REMOVAL	FOOT	1,269

FILE NAME = I:\Users\cra\08224871\Draw\Sheet\SD01.B3.dgn

**CMT**  
 CRAWFORD, MURPHY & TILLY, INC.  
 CONSULTING ENGINEERS  
 License No. 184-000613

USER NAME = Monica Crivison  
 PLOT SCALE = 1:8000' / IN.  
 PLOT DATE = 07/15/09

DESIGNED - SJP  
 DRAWN - SJP  
 CHECKED - KDN  
 DATE - 07/15/09

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -



SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1016	02-00110-12-WR	LAKE	206	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				CONTRACT NO. 63209