

7. SCHEDULE OF CURB & GUTTER AND RELATED ITEMS

FROM	TO	60603800 COMB CC&G TB6.12 FOOT	60605000 COMB CC&G TB6.24 FOOT	60608300 COMB CC&G TM2.12 FOOT	60619200 CONC MED TSB6.06 SQ FT	60624600 CORRUGATED MED SQ FT	44000500 COMB CURB GUTTER REM FOOT	44003100 MEDIAN REMOVAL SQ FT	44003800 MEDIAN SURF REMOVAL SQ FT
WASHINGTON STREET									
131+00	137+00		595						
137+00	143+00	16	1216		224	37	288		
143+00	149+00	50	1200				39		
149+00	155+00		1205						
155+00	161+00	196	1200						
161+00	167+00	373	1200				92	297	
167+00	173+00		1200		141	22	691	3739	
173+00	179+00	714	1229		492	186	1977	404	
179+00	10+00	151	170	694			1037	2548	8114
TRI-STATE PARKWAY									
16+00	20+00	16	26		1253	37		80	
TOTALS		1516	9241	694	2110	282	4513	7068	8114

8. SCHEDULE OF SIDEWALK AND RELATED ITEMS

FROM	TO	LT OR RT	42400100 PC CONC SIDEWALK 4 SQ FT	XX006652 STAMP CLRD PCC MED 4 SQ FT	42400800 DETECTABLE WARNINGS SQ FT
WASHINGTON STREET					
131+00	137+00	LT			
		RT			
137+00	143+00	LT	224		32
		RT	112		16
143+00	149+00	LT			
		RT			
149+00	155+00	LT			
		RT			
155+00	161+00	LT		960	
		RT			
161+00	167+00	LT		1755	
		RT			
167+00	173+00	LT			
		RT			
173+00	179+00	LT	336		48
		RT	224		32
179+00	10+00	LT			
		RT			
TRI-STATE PARKWAY					
16+00	20+00	LT			
		RT			
TOTAL SQUARE FEET			896	2715	128
TOTAL SQUARE YARDS					
TOTALS			896	2715	128

9. SCHEDULE OF TEMPORARY PAVEMENT AND RELATED ITEMS

FROM	TO	X0712400 TEMP PAVEMENT SQ YD	40600990 TEMP PAVEMENT RAMP SQ YD				40201100 AGGREGATE-TEMP ACCESS TON				
		PRE-STAGE	STAGE 1B	STAGE 1C	STAGE 2A	STAGE 2B	STAGE 2C	PRE-STAGE	STAGE 1A	STAGE 2A	STAGE 2C
WASHINGTON STREET											
127+75	141+00	1246			15		7		42		
141+00	156+00	2355	25	12	9	42		34		45	114
156+00	171+00	565								135	
171+00	10+00	1558	22	14	21		15			304	
TRI-STATE PARKWAY											
15+00	22+00	393	11	53	69						
STAGE TOTAL		6117	58	79	114	42	22	34	42	484	114
TOTAL		6117			315					674	

FILE NAME = I:\lakeco\0822481\pav\sheeta\SCDL_04.dgn



USER NAME = Jeff Sedig
 DESIGNED - SJP
 DRAWN - SJP
 CHECKED - KDN
 DATE - 05/29/09

REVISED -
 REVISED -
 REVISED -
 REVISED -



SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 4 OF 10 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1016	02-00110-12-WR	LAKE	206	13
CONTRACT NO. 63209				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				