

13. SCHEDULE OF PAVEMENT REMOVAL AND RELATED ITEMS

FROM	TO	LT	OR	40600982 HMA SURF REM BUTT JT SQ YD	44000100 PAVEMENT REM SQ YD	44000155 HMA SURF REM 1 1/2 SQ YD	44000200 DRIVE PAVEMENT REM SQ YD	44004250 PAVED SHLD REMOVAL SQ YD
WASHINGTON STREET								
131+00	137+00	LT		900	6578	1181	1166	115
		RT		900	6480	5981		112
137+00	143+00	LT			15930	2400		1147
		RT			10797	11979	2136	1202
143+00	149+00	LT			9135	499		505
		RT			8810	8175		520
149+00	155+00	LT			7055		740	
		RT			10061	9172	2043	
155+00	161+00	LT			253			
		RT			16625	14502	1420	
161+00	167+00	LT			684		865	
		RT			19335	16564	1493	191
167+00	173+00	LT			11890			157
		RT			16704	15932	2148	1936
173+00	179+00	LT		249	22785			5036
		RT		273	16675	16143	902	1917
179+00	10+00	LT			2515			765
		RT			2480	1701	682	102
TRI-STATE PARKWAY								
16+00	20+00	LT		454	742	3498		
		RT		455	741	3518		
TOTAL SQUARE FEET				3231	186275	111245	13595	13705
TOTAL SQUARE YARDS				359	20697	12361	1511	1523
TOTALS				359	20697	12361	1511	1523

14. SCHEDULE OF HMA AND RELATED ITEMS

FROM	TO	LT	OR	40603080 HMA BC IL-19.0 N50 TON	40603085 HMA BC IL-19.0 N70 TON	40603240 P HMA BC IL19.0 N90 TON	40603595 P HMA SC "F" N90 TON	40603335 HMA SC "D" N50 TON	40603340 HMA SC "D" N70 TON	40600100 BIT MATLS PR CT GALLON			
WASHINGTON STREET													
131+00	137+00	LT		3051	178	8497	8497	3051	438	178	1181		
		RT			1183	8497	8497			1183	5981		
137+00	143+00	LT		5016		24672	24672	5016			2400		
		RT			2310	17569	17569	628	2310	11979	17569		
143+00	149+00	LT		6252		20385	20385	6252			499		
		RT			2393	17561	17561			2393	17561		
149+00	155+00	LT		6242		17550	17550	6242			17550		
		RT			2380	17586	17586	410	2380	9172	17586		
155+00	161+00	LT		6852		17171	17171	6852			17171		
		RT			2561	17148	17148	358	2561	14502	17148		
161+00	167+00	LT		7626		17330	17330	7626			17330		
		RT			2518	17329	17329	791	2518	16564	17329		
167+00	173+00	LT		6259		18603	18603	6259			18603		
		RT			2354	18772	18772	1237	2354	15932	18772		
173+00	179+00	LT		5283		22354	22354	5283			22354		
		RT			4574	15850	15850	741	4574	16143	15850		
179+00	10+00	LT		1002		2076	2076	1002			2076		
		RT			2603	2004	2004	554	2603	1701	2004		
TRI-STATE PARKWAY													
16+00	20+00	LT			2111					3496	2111		
		RT			1047					3517	1047		
TOTAL SQUARE FEET				47583	28440	3158	280954	280954	47583	5157	28440	111242	
TOTAL SQUARE YARDS				5287	3160	351	31217	31217	5287	573	3160	284112	
112 LBS/SY/INCH CONV.				112	112	112	112	112	112	112	112	31568	
APP. RATE (GAL/SQ YD)											0.1	0.1	
LIFT THICKNESS (INCHES)				2	2.5	10.5	10.5	1.5	2	2.5	1.5	1.5	
GALLONS												3156	
TONS (LBS/2000)				592	442	206	18356	2622	592	81	266	1038	
TOTALS				1034	206				938			1068	5237

FILE NAME: L:\PROJECTS\0822\01\Drawings\Sheet13\SCD_07.dgn

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 084-000613

USER NAME = Jeff Sedig	DESIGNED - SJP	REVISED -
PLOT SCALE = 1:0000' / 1" =	DRAWN - SJP	REVISED -
PLOT DATE = 05/29/09	CHECKED - KDN	REVISED -
	DATE - 05/29/09	REVISED -



SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 7 OF 10 SHEETS	STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1016	02-00110-12-WR	LAKE	206	16
CONTRACT NO. 63209				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				