

ITEM NO.	PAY ITEM	UNIT	TOTAL QUANTITY Y047	SEGMENT A (KINGSBURY LANE)	SEGMENT B (KENSINGTON LANE)	SEGMENT C (NORTHWAY DRIVE)	SEGMENT D (SPUR)
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	15	0	0	15	0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	108	0	0	108	0
20100500	TREE REMOVAL, ACRES	ACRE	0.4	0	0.2	0.2	0
20101100	TREE TRUNK PROTECTION	EACH	2	0	0	2	0
20200100	EARTH EXCAVATION	CU YD	362	137	32	187	6
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	37	9	52	2
20400800	FURNISHED EXCAVATION	CU YD	120.7	81.5	25.2	10	4
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	90	5	5	75	5
20800150	TRENCH BACKFILL	CU YD	10	0	0	10	0
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	6364	1953	1420	2682	309
21101625	TOPSOIL, FURNISH AND PLACE, 6 INCH	SQ YD	3183	977	710	1341	155
25000210	SEEDING, CLASS 2A	ACRE	0.66	0.2	0.15	0.28	0.03
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	59.4	18.2	13.2	25	3
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	59.4	18.2	13.2	25	3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	59.4	18.2	13.2	25	3
25100115	MULCH METHOD 2	ACRE	0.66	0.2	0.15	0.28	0.03
25100401	EXCELSIOR BLANKET, SPECIAL	SQ YD	3194	968	726	1355	145
28000400	PERIMETER EROSION BARRIER	FOOT	9850	3022	2197	4150	481
28000510	INLET FILTERS	EACH	3	1	1	1	
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	115.5	38.5	38.5	38.5	0
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	5305	1628	1183	2236	258
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1326	407	296	559	64
40600300	AGGREGATE (PRIME COAT)	TON	10.62	3.26	2.37	4.47	0.52
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	892	274	199	376	43
42000400	PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	2	0	0	2	0
42001300	PROTECTIVE COAT	SQ YD	215	38	139	38	0
42400800	DETECTABLE WARNINGS	SQ FT	80	16	32	32	0
44000100	PAVEMENT REMOVAL	SQ YD	32	0	0	32	0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	75	15	30	30	0
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	0	0	1	0
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	0	2	0	0
54010603	PRECAST CONCRETE BOX CULVERT 6'X3'	FOOT	25	0	25	0	0
54213483	END SECTIONS 48"	EACH	1	0	0	1	0
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	0	0	0	1
54248510	CONCRETE COLLAR	CU YD	11.4	0	0	11.4	0
55022600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 48"	FOOT	58	0	0	58	0
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	70	0	0	70	0
56109210	WATER VALVES TO BE ADJUSTED	EACH	2	0	0	2	0
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	0	0	0	1
66400205	CHAIN LINK FENCE, 5'	FOOT	40	0	0	40	0
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	20	0	0	20	0
66410900	CHAIN LINK GATES TO BE REMOVED AND RE-ERECTED	EACH	2	0	0	2	0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO.	2	2	0	0	0
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	L SUM	1	0.25	0.25	0.25	0.25
72000100	SIGN PANEL - TYPE 1	SQ FT	62.5	31.25	25	6.25	0
72900100	METAL POST - TYPE A	FOOT	72	24	24	24	0
72900200	METAL POST - TYPE B	FOOT	81	27	27	27	0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	195	65	65	65	0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	156	56	50	50	0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	274	97	87	90	0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4825	1465	1065	2015	280
Z0064600	SELECTIVE CLEARING	ACRE	0.1	0	0	0.1	0
XX002906	TIP DOWN GATE	EACH	6	2	2	2	0
XX006066	SIGN TO BE RELOCATED	EACH	10	2	2	6	0
* XX008134	VENT (AIR HORN) PIPES TO BE RELOCATED	EACH	2	0	0	2	0
* XX008135	CATHODIC PROTECTION SYSTEM TESTING	L SUM	5	2	2	1	0

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

URS 100 S. WACKER DR., SUITE 500 TEL (312)-939-1000
CHICAGO IL, 60606 FAX (312)-939-4198

VILLAGE OF HANOVER PARK
N.G.P.L. BIKE PATH
SUMMARY OF QUANTITIES

SCALE: DRAWN BY: VAP
DATE: CHECKED BY: TOO