



LOOKING NORTHBOUND ALONG WOLF RD. AT EXISTING LIGHT POLE L-7

EXISTING LIGHT POLE L-7

LEGEND

- EXISTING 400W HIGH PRESSURE SODIUM (HPS) COBRA HEAD TYPE LUMINAIRE WITH TYPE III OPTICS MOUNTED 45'-0" ABOVE GRADE ON A SPUN ALUMINUM LIGHT POLE WITH A 15'-0" TRUSS TYPE MAST ARM
- PROPOSED 35W HPS ACORN TYPE ORNAMENTAL LUMINAIRE WITH TYPE V OPTICS MOUNTED 14'-0" ABOVE GRADE ON AN EXISTING LIGHT POLE
- EXISTING ELECTRICAL CABLES IN UNIT DUCT AS SHOWN ON PLANS
- PROPOSED ORNAMENTAL LUMINAIRE NUMBER
- PL-1, CKT B ← LIGHTING CIRCUIT IDENTIFIER
- EX. L-7, CKT A ← EXISTING LIGHT POLE NUMBER
- EX. L-7, CKT A ← LIGHTING CIRCUIT IDENTIFIER
- EXISTING SANITARY SEWER
- EXISTING STORM SEWER
- EXISTING WATERMAIN
- EXISTING OVERHEAD WIRES
- EXISTING GAS LINE

NOTES:

1. CONTRACTOR SHALL INSTALL A NEW ORNAMENTAL TYPE LUMINAIRE ON EXISTING LIGHT POLES WHERE SHOWN ON PLAN DRAWINGS, AND AS DESCRIBED IN THE DETAIL DRAWING & SPECIAL PROVISION.
2. WORK REQUIRED TO INSTALL PROPOSED LUMINAIRES SHALL BE COMPLETED WITHIN THE SAME DAY. NO LUMINAIRES WILL BE ALLOWED TO BE LEFT WITHOUT POWER OVERNIGHT.
3. CONTRACTOR SHALL CONTACT THE CITY OF NORTHLAKE POLICE DEPARTMENT TO COORDINATE ANY POWER INTERRUPTION/TEMPORARY REMOVAL OF EXISTING POLE MOUNTED ANTENNA AND CAMERA (SEE PHOTO THIS SHEET.)
4. CONTRACTOR SHALL TAKE PARTIAL MAINTENANCE OF EXISTING LIGHTING SYSTEM, OF ONLY THE CIRCUITS THAT ARE AFFECTED, DURING CONSTRUCTION OF THIS CONTRACT. THIS WORK SHALL INCLUDE MAINTENANCE OF LIGHTING UNITS, CABLE RUNS AND ANY EQUIPMENT MOUNTED TO THEM. IN CASE OF POLE KNOCKDOWN OR EQUIPMENT DAMAGED BY EITHER MOTORING PUBLIC OR CONTRACTOR OPERATIONS, THE CONTRACTOR SHALL CLEAR AND RESTORE THE EXISTING SYSTEM TO ORIGINAL CONDITION (SEE CONTRACT SPECIFICATIONS).

FILE NAME =	USER NAME = EDT00A	DESIGNED - KB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED LIGHTING PLAN WOLF ROAD	F.A. RTE. 2690	SECTION 09-00069-00-SP	COUNTY COOK	TOTAL SHEETS 28	SHEET NO. 10		
N:\NORTHLAKE\940632DC95\Meach\LGT_940632DC95_02.sht	PLOT SCALE = 3/8"	CHECKED - AJD	REVISED -			SCALE: 1"=30'-0"	SHEET NO. 10 OF 28 SHEETS	STA. 9+40	TO STA. 16+70	ILLINOIS FED. AID PROJECT		
PLOT DATE = 7/6/2009	DATE = 03/27/09	REVISED -	REVISED -			CONTRACT NO. 63222						