FAU RTE 1369	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCHICK RD.	09-00057-00-RS	DUPAGE	15	4
F.H.W.A. REG.	ILLINOIS	PROJECT NO. ARA-9003(440)		

CONTRACT NO. 63252

	CODE NO.	ITEM	UNIT	QUANTITY 1000	NON-PARTICIPATING ITEM	
	20200500	EARTH EXCAVATION, (WIDENING)	CU YD	50		
	20400800	FURNISHED EXCAVATION	CU.YD.	60		
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8000		
	25000400	NITROGEN FERTILZER NUTRIENT	POUND	150		
	25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	150		
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	150		
	25200110	SODDING, SALT TOLERANT	SQ YD	8000		
	25200200	SUPPLEMENTAL WATERING	UNITS	10		
	35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	280		
	35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	130		
	40600895	CONSTRUCTING TEST STRIP	EACH	1		
	40600982	HOT-MIX ASPHALT SURFACE REM.- BUTT JOINT	SQ YD	500		
	40800010	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1653		
	40800030	AGGREGATE (PRIME COAT)	TON	33		
	40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	80		
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3240		
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	150		
	42001300	PROTECTIVE COAT	SQ YD	4686		
	42300710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH (SPECIAL)	SQ YD	120		○
	42400800	DETECTABLE WARNINGS	SQ FT	350		
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1200		○
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	120		
	44001700	COMBINATION CONCRETE CURB & GUTTER REMOVAL AND REPLACEMENT	FOOT	12700		○
	44002800	ISLAND PAVEMENT REMOVAL	SQ YD	975		○
	44004610	SIDEWALK REMOVAL & REPLACEMENT (SPECIAL)	SQ FT	2500		○
	44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	1200		
	44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	2400		
	44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	2200		
	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	8		
	60234200	INLET,TYPE A, TYPE 1 FRAME AND OPEN LID	EACH	1		
	60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	27		
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	16		○
	60404400	FRAMES AND GRATES, TYPE 4	EACH	1		
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1		
	67100100	MOBILIZATION	L SUM	1		
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		
	70300100	SHORT-TERM PAVEMENT MARKINGS	FOOT	50000		
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	500		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24000		
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3500		
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	300		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200		
*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1		
*	88600600	DETECTOR LOOP RELACEMENT	FOOT	500		○
	Z0075300	TIE BARS	EACH	1750		○
	Z0017202	DOWEL BARS 1 1/2"	EACH	1250		○
△	Z007600	TRAINEES	HOUR	500		
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2314		
*	XX006257	RECESSED REFLECTIVE PAVEMENT MARKERS	EACH	592		○
	X008127	STAMPED ASPHALT	SQ YD		280	○

△ Y080

* SPECIALTY ITEM

○ SPECIAL PROVISION ASSOCIATED WITH THIS ITEM

PREPARED BY: VILLAGE OF BLOOMINGDALE
201 S. BLOOMINGDALE RD.
BLOOMINGDALE ILLINOIS 60108
(630) 893-7073

PROJECT NAME: 2009 SCHICK ROAD RESURFACING

SUMMARY OF QUANTITIES

DATE: 12-12-08
SCALE: NTS
DRAWN BY: B.P.S.
APPROVED BY:

REVISIONS
1. 2. 3. 4. 5. 6.

SHEET NO. 4/15