

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	QUANTITY (1000)
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,107
40600300	AGGREGATE (PRIME COAT)	TON	42
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	885
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	183
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,032
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	78
42400800	DETECTABLE WARNINGS	SQ FT	6
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	10,533
44000600	SIDEWALK REMOVAL	SQ FT	78
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	508
44200089	PAVEMENT PATCHING, TYPE I, 8 INCH	SQ YD	228
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	228
44200099	PAVEMENT PATCHING, TYPE III, 8 INCH	SQ YD	228
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SQ YD	228
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	10,533
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	42
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	128
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,284
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,900
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	314
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	295
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,830
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	128
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,284
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,900
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	314
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	295
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	636
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	300

• SPECIALTY ITEMS