

SUMMARY OF QUANTITIES

	CODE	PAY ITEM DESCRIPTION	UNIT	1000 TOTAL QUANTITY	1000 100% FEDERAL 0% LOCAL
⊗	20800150	TRENCH BACKFILL	CU YD	40	40
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	700	700
	25200100	SODDING	SQ YD	700	700
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2,040	2,040
	40600300	AGGREGATE (PRIME COAT)	TON	30	30
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	275	275
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,200	1,200
	42101300	PROTECTIVE COAT	SQ YD	770	770
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	150	150
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4,180	4,180
⊗	42400800	DETECTABLE WARNINGS	SQ FT	75	75
⊗	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10,160	10,160
⊗	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	150	150
⊗	44000600	SIDEWALK REMOVAL	SQ FT	4,180	4,180
⊗	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	710	710
⊗	44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	560	560
⊗	44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	580	580
⊗	60213900	RESTRICTED DEPTH CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	6	6
⊗	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3
⊗	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	18	18
⊗	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	11	11
	67100100	MOBILIZATION	L SUM	1	1
⊗	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	500	500
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	50	50
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,750	4,750
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	280	280
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	220	220
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	220	220
*⊗	88600600	DETECTOR LOOP REPLACEMENT	FOOT	100	100
⊗	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	790	790
⊗	XX003424	CONNECTION TO EXISTING STRUCTURE	EACH	1	1
⊗	XX005688	STORM SEWERS, DUCTILE IRON PIPE, CLASS 52 8"	FOOT	29	29
⊗	XX005689	STORM SEWERS, DUCTILE IRON PIPE, CLASS 52 10"	FOOT	26	26
⊗	XX005770	STRUCTURE TO BE ABANDONED	EACH	5	5

* SPECIALTY ITEMS

Drawing file: W:\Projects\56500072 - 9TH Avenue_ARA-LAPP\Summary.dwg Jul 17, 2009 - 9:48am



910 Riverside Road
Waukegan, Illinois 60087-1700
Phone: 815-496-4300
Fax: 815-496-1232

USER NAME	DESIGNED CH	REVISED	
	DRAWN MK	REVISED	
PLOT SCALE	CHECKED CH	REVISED	
PLOT DATE	DATE 4-21-09	REVISED	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2733	09-00131-00-RS	COOK	17	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63255	
			ARA-9003(319)	

E.H.E. PROJECT NO. 565-09-07201