

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL	F BRF A		
				80% FEDERAL 20% STATE 096-2011 X028-2A	80% FEDERAL 20% STATE 096-0071 X071-2A	80% FEDERAL 20% STATE 096-0072 X071-2A
50501005	JACK AND REPOSITION BEARINGS	EACH	1		1	
50800105	REINFORCEMENT BARS	POUND	30940	30940		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	70010		28460	41550
50800515	BAR SPLICERS	EACH	898	125	336	437
51201800	FURNISHING STEEL PILES HPI4X73	FOOT	1638			1638
51202000	FURNISHING STEEL PILES HPI4X102	FOOT	1120		1120	
51202305	DRIVING PILES	FOOT	2758		1120	1638
51203800	TEST PILE STEEL HPI4X73	EACH	4			4
51204000	TEST PILE STEEL HPI4X102	EACH	2		2	
51205200	TEMPORARY SHEET PILING	SQ FT	3556		1778	1778
51500100	NAME PLATES	EACH	3	1	1	1
52100520	ANCHOR BOLTS, 1"	EACH	72		24	48
54003000	CONCRETE BOX CULVERTS	CU YD	181.0	181.0		
542C1087	PIPE CULVERTS, CLASS C, TYPE 2 42"	FOOT	74		74	
542C1093	PIPE CULVERTS, CLASS C, TYPE 2 48"	FOOT	65		65	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	44		44	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	98		98	
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	88	50		38
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	18		18	
54201303	PIPE CULVERTS, TYPE 2 RCCP 48"	FOOT	167		167	
54213453	END SECTIONS 18"	EACH	2		2	
54213459	END SECTIONS 24"	EACH	7		5	2
54213471	END SECTIONS 36"	EACH	4	2		2
54213477	END SECTIONS 42"	EACH	2		2	
54213483	END SECTIONS 48"	EACH	1		1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		1	
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1		1	
54217722	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 24" RISER	EACH	1		1	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	178	178		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	158		93	65
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	400		273	127
60801024	FLAP GATE 24"	EACH	1		1	
60801048	FLAP GATE 48"	EACH	2		2	
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1087.5		400.0	687.5
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8		4	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	6		3	3
63200310	GUARDRAIL REMOVAL	FOOT	1195	638	198	359
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	150		150	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	25	8	16	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5		2	3
67100100	MOBILIZATION	L SUM	1		0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.3	0.3	0.4
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		0.5	0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		0.5	0.5

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = rcook
P:\034060\104.FIN0960055\Drawings\QuantitiesSummary.dgn	
PLOT SCALE = 20.000' / 1" IN.	
PLOT DATE = 3/26/2009	

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.	F.A.P. RTE. 823	SECTION (22BY-1,22BY2,22BR)B-1	COUNTY WAYNE	TOTAL SHEETS 142	SHEET NO. 4
				CONTRACT NO. 74238				
				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				