

LOCATION	THERMOPLASTIC PAVEMENT MARKING					RAISED REFLECTIVE PAVEMENT MARKERS	PAVEMENT MARKING REMOVAL SQ. FT.
	LETTERS AND SYMBOLS SQ. FT.	SOLID WHITE 4" LIN. FT.	SKIP-DASH WHITE 4" LIN. FT.	WHITE 8" LIN. FT.	WHITE 12" EACH	ONE WAY CRYSTAL EACH	
STATION TO STATION							
243+66.00	8.8						
244+46.00	8.8						
245+26.00	8.8						
246+06.00	8.8						
246+86.00	8.8						
243+66.00	8.8						
242+49.08 - 249+10.00		800					
247+76.96 - 249+10.00			44				
ILLINOIS ROUTE 1							
242+53.09 - 247+76.96				524			
242+53.89 - 247+76.96				556			
HUTSONVILLE ROAD							
0+12.16 - 1+00.00				88			
242+53.09 - 247+76.96					535		
243+78.00						2	
244+18.00						2	
244+58.00						2	
244+98.00						2	
245+38.00						2	
245+78.00						2	
246+18.00						2	
246+58.00						2	
246+98.00						2	
247+38.00						2	
247+78.00						1	
							90
242+95.00 - 245+65.00							
TOTALS	52.8	800	44	1168	535	21	90
GRAND TOTALS	52.8		844	1168	535	21	90

FILE NAME =	USER NAME = moakley	DESIGNED -	REVISED -
P:\0340702\hutsonville\Drawings\planprof\pavementmarking.dgn		DRAWN -	REVISED -
FLOT SCALE - 50.0000 ' / IN.		CHECKED -	REVISED -
FLOT DATE = 12/16/2008		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**PAVEMENT MARKING SCHEDULE**

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	22N	CRAWFORD	22	11
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 74300	