

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE								
			URBAN 90/10 FED/ST TOTAL QUANTITIES	MAINLINE ROADWAY 1000	TR 162 E 060-0172 SFTY-2A	IL 159 060-0269 SFTY-2A	I-55/70 060-0018/19 SFTY-2A	US 40 060-0267 SFTY-2A	I-70 WB 060-0022 SFTY-2A	I-270 EB/WB 060-0057/58 SFTY-2A	SIGNS Y002-1C
CODE NO	ITEM	UNIT									
20100500	TREE REMOVAL, ACRES	ACRE	6.82	6.82							
20400800	FURNISHED EXCAVATION	CU YD	105	105							
21400100	GRADING AND SHAPING DITCHES	FOOT	900	900							
25000200	SEEDING, CLASS 2	ACRE	10.5	10.5							
25100115	MULCH, METHOD 2	ACRE	10.5	10.5							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1050	1050							
28100101	STONE RIPRAP, CLASS A1	SQ YD	12			12					
28100107	STONE RIPRAP, CLASS A4	SQ YD	261	261							
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	178	178							
28200200	FILTER FABRIC	SQ YD	273	261		12					
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	3407	3407							
35300720	PORTLAND CEMENT CONCRETE BASE COURSE 13"	SQ YD	2904	2904							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	134.4	134.4							
40600300	AGGREGATE (PRIME COAT)	TON	641.8	641.8							
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2908	2908							
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	928	928							
40600990	TEMPORARY RAMP	SQ YD	1152	1152							
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	29019	29019							
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	21	21							
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	35912	35912							
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	239616	239616							
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	15681	15681							
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1286	1286							
44004250	PAVED SHOULDER REMOVAL	SQ YD	2341	2341							
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	77.1	77.1							
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	330	330							
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	350.1	350.1							
44201903	CLASS D PATCHES, TYPE III, 21 INCH	SQ YD	40	40							
44213100	PAVEMENT FABRIC	SQ YD	680.1	680.1							
44213200	SAW CUTS	FOOT	2294	2294							
45200300	JOINT OR CRACK FILLING	POUND	192		36	156					

Rev. 9-8-09

Rev. 8-31-09

*60-(7,8,9,10)RS, 60-(8,9,10)BR

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.T. RTE. 70	SECTION .	COUNTY MADISON	TOTAL SHEETS 150	SHEET NO. 3
ca:\pwwork\KPMIDOT\CONOVERPJ\dms71873\d876a73-shr-plen.dgn	76a73-shr-plen.dgn	DRAWN -	REVISED -			CONTRACT NO. 76A73				
PLOT SCALE = 58,0000' / IN.	DATE = 6/25/2009	CHECKED -	REVISED -		SCALE: _____	SHEET NO. 1 OF 6 SHEETS		STA. _____ TO STA. _____		
		DATE -	REVISED -			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				