

CONTRACT NO. 83827				
F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3570	00-00116-00-BR	DUPAGE	106	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE				
				80% FED / 20% CITY OF NAPERVILLE			100% CITY OF NAPERVILLE	
				ROADWAY	BRIDGE	LIGHTING	ELECTRIC	LANDSCAPING
CODE NO.	ITEM		1000-2A	X071-2A	Y030-1E	Y030-1E	Y003	
Z0015500	DEBRIS REMOVAL	L SUM	1	1				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3				
Z0022800	FENCE REMOVAL	FOOT	25	25				
Z0054400	ROCK FILL	CU YD	262		262			
Z0062000	SAW CUTTING	FOOT	8	8				
X5428878	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 78" (SPECIAL)	EACH	1	1				
* K0039111	CHAENOMELES SPECIOSA 'TEXAS SCARLET', 18"C	EACH	40					40
XX008136	HDPE SANITARY SEWER BEND, 45 DEGREE, 3"	EACH	2	2				
K1004490	PINEBARK FINES MULCH	CU YD	3					3
XX008137	PROVIDE AND INSTALL DOUBLE BANNER POLE	EACH	1					1
* XX008138	RELOCATE EXISTING METAL LIGHT POLE FOUNDATION	EACH	4	4				
XX008139	REMOVE AND RELOCATE EXISTING MEMORIAL STONE	L SUM	1	1				
XX008140	REMOVE AND RELOCATE EXISTING PLAQUE	EACH	1	1				
K1004600	REMOVE PERENNIALS	EACH	40	40				
* A2008140	TILIA CORDATA 'GREENSPIRE', 5.0"	EACH	1					1
* XX008141	STANDOFF RISER ASSEMBLY 6"	EACH	1			1		
* XX008142	10 WAY 8-6" & 2-3" PVC DUCT BANK-4 HIGH BY 3 WIDE	FOOT	170			170		
* XX008143	9 WAY 7-6" & 2-3" PVC DUCT BANK-2 HIGH BY 7 WIDE	FOOT	10			10		
* XX008144	4 WAY 2-3" & 2-6" PVC DUCT BANK-2 HIGH BY 2 WIDE	FOOT	20			20		
20200205	ROCK EXCAVATION (SPECIAL)	CU YD	50			50		
* XX008145	SANITARY FORCEMAIN REMOVAL, 3"	FOOT	214	214				
* XX008146	SANITARY SEWER, HDPE FORCEMAIN, 3"	FOOT	105	105				
* XX008147	SANITARY SEWER, PVC SDR 21, 8"	FOOT	137	137				
* K1004610	SEASONAL ANNUALS	SQ FT	67					67
* XX008148	UNIT DUCT WITH 4/C NO. 6 (XLP-TYPE USE), DIRECTIONAL BORING, 1/4"	FOOT	863	863				
* K0040350	WALDSTENIA FRAGARIOIDES, 3" POT	EACH	480	480				
* XX008149	ROUGH GRADING	SQ YD	100					100
* K1004700	ACCENT BOULDER, 30"	EACH	2					2
* XX008160	DECORATIVE LIGHTING SYSTEM COMPLETE	L SUM	1					1
XX008159	PORTLAND CEMENT CONCRETE BAND FOR PAVER BRICKS	FOOT	56	56				
X6060150	CONCRETE CURB 6", REINFORCED	FOOT	206	206				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE
PER DEC & CLIENT	9/13/05
PER IDOT	11/1/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

JEFFERSON AVENUE OVER
WEST BRANCH DUPAGE RIVER

SCALE: NO SCALE
DATE: JULY 10, 2009
DRAWN BY
CHECKED BY HRT