

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: X081-2A

PAY CODE	QUANTITY	UNIT	ITEM
20100110	24	Unit	Tree Removal (6 to 15 Units Diameter)
20100210	16	Unit	Tree Removal (Over 15 Units Diameter)
* 20200410	1,278	Cu. Yd.	Earth Excavation (Special)
20300100	330	Cu. Yd.	Channel Excavation
* 20700220	19	Cu. Yd.	Porous Granular Embankment
* 25001100	1.17	Acre	Seeding, Class 3 (Special)
25100630	5,663	Sq. Yd.	Erosion Control Blanket
28000300	16	Each	Temporary Ditch Checks
28000400	80	Foot	Perimeter Erosion Barrier
* 28100209	1,490	Ton	Stone Riprap, Class A5
* 40200100	1,471	Ton	Aggregate Surface Course, Type A
* 40200800	160	Ton	Aggregate Surface Course, Type B
50100100	1	Each	Removal of Existing Structures
* 50300225	27.4	Cu. Yd.	Concrete Structures
* 50400505	1,600	Sq. Ft.	Precast Prestressed Concrete Deck Beams (27" Depth)
50800105	2,780	Pound	Reinforcement Bars
Δ50901050	136	Foot	Steel Railing, Type SM
51200957	265	Foot	Furnishing Metal Shell Piles 12"x0.250"
* 51202305	265	Foot	Driving Piles
51203200	1	Each	Test Pile Metal Shells
51500100	1	Each	Name Plates
54200643	82	Foot	Pipe Culverts, Type 1, Corrugated Steel or Aluminum Culvert Pipe 18"
54200649	38	Foot	Pipe Culverts, Type 1, Corrugated Steel or Aluminum Culvert Pipe 24"
54205929	42	Foot	Pipe Culverts, Type 1, Corrugated Steel, Equivalent Round-Size 54"
54213873	4	Each	Steel End Sections 18"
54213879	2	Each	Steel End Sections 24"
54215169	2	Each	Steel End Sections, Equivalent Round-Size 54"
* 60107700	1,612	Foot	Pipe Underdrains 6"
67100100	1	L. Sum	Mobilization
* 70101700	1	L. Sum	Traffic Control And Protection
* Z0013798	1	L. Sum	Construction Layout

* See Special Provisions.
Δ Specialty Items

FILE NAME = s:\shu\1115000\Drawing\1115Summary_of_Quantities.dgn

WILLET, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
 808 East Second Street Dixon, IL 61021
 Phone 815.284.3381 Fax 815.284.3385
 Design Firm # 184-00918
 www.willett-hofmann.com

USER NAME =	DESIGNED - MAS	REVISED -
	DRAWN - RDA	REVISED -
PLOT SCALE =	CHECKED - BKC	REVISED -
PLOT DATE =	DATE - 06/09	REVISED -

BUREAU COUNTY
MINERAL ROAD DISTRICT
TR 257 (N. 1600 AVE.) OVER KING CREEK

SUMMARY OF QUANTITIES

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
257	07-17137-00-BR	BUREAU	27	2
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT BR05-001107D			CONTRACT NO. 87381	