

GENERAL NOTES

Existing structures (including foundations, walls, cisterns, wells or other underground structures) within the right of way shall be removed in accordance with Article 501.02 and 501.03 of the Standard Specifications, without additional compensation, unless otherwise noted in the plans or special provisions.

The Contractor shall seed all disturbed areas within the project limits.

No overhaul has been computed and none shall be paid for from any source.

The final top four inches of soil in any right of way area disturbed by the Contractor must be a cohesive soil capable of supporting vegetation.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications.

The utilities located within the project limits or immediately adjacent to the project construction limits include:

Ameren IP Attn: Ms. Kathy Cromwell 1450 Red Adams Road Kewanee, IL 61443 (309) 852-2963	Henry County Telephone Attn: Mr. Matt Storm 111 E. 1st St. Geneseo, IL 61254 (309) 944-2103	Verizon North, Inc. Attn: Terry Spurgeon 111 S. Main St. Kewanee, IL 61443 (309) 853-6293
---	---	---

AT&T Attn: Mr. Keith Heimlick (815) 774-6762	Mediacom Attn: Mr. John Smith 900 26th Ave. Moline, IL 61265 (309) 314-0902
--	---

A minimum of 48 hours advance notice is required for non-emergency work.

A nation wide permit has been issued for this project and the conditions of that permit must be adhered to.

Where section or subsection monuments are encountered, the Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all property markers, monuments and right of way pins until the Owner, an Authorized Surveyor, or Agent has witnessed or otherwise referenced their location.

Existing mail boxes, street signs and traffic signs that are within the construction limits shall be removed and reset by the Contractor. Cost of removing and resetting to be included in the contract unit price bid per Cubic Yard for Earth Excavation.

SCHEDULE OF QUANTITIES - CONT.

EROSION CONTROL BLANKET

LOCATION	SQ. YD.	REMARKS
RT. STA. 12+00 - 15+50	1065	
RT. STA. 15+50 - 19+11	1210	
LT. STA. 15+50 - 19+16	1065	
RT. STA. 19+37 - 19+98	145	
LT. STA. 19+36 - 20+00	97	
RT. STA. 20+15 - 20+73	97	
LT. STA. 20+26 - 20+90	145	
RT. STA. 20+99 - 24+00	968	
LT. STA. 21+08 - 24+00	871	
TOTAL	5663 SQ. YD.	

TEMPORARY DITCH CHECKS

LOCATION	EACH	REMARKS
RT. STA. 12+50	1	
RT. STA. 13+50	1	
RT. STA. 14+50	1	
RT. STA. 15+50	1	
LT. & RT. STA. 16+50	2	
LT. & RT. STA. 17+50	2	
LT. & RT. STA. 18+50	2	
LT. & RT. STA. 21+50	2	
LT. & RT. STA. 22+50	2	
LT. & RT. STA. 23+50	2	
TOTAL	16 EACH	

PERIMETER EROSION BARRIER

LOCATION	FOOT	REMARKS
RT. STA. 19+77 - 19+97	20	
LT. STA. 19+80 - 20+00	20	
RT. STA. 20+14 - 20+34	20	
LT. STA. 20+26 - 20+46	20	
TOTAL	80 FOOT	

AGGREGATE SURFACE COURSE, TYPE A

LOCATION	TON	REMARKS
STA. 15+50 - 16+27.50	97	TAPER 15" COMPACTED
STA. 16+27.50 - 19+76	705	15" COMPACTED
STA. 20+44 - 23+47.50	576	15" COMPACTED
STA. 23+47.50 - 24+00	93	TAPER 15" COMPACTED
TOTAL	1471 TON	

AGGREGATE SURFACE COURSE, TYPE B

LOCATION	TON	REMARKS
F.E.R. STA. 19+24	46	8" COMPACTED
F.E.L. STA. 19+26	32	8" COMPACTED
F.E.R. STA. 20+87	49	8" COMPACTED
F.E.L. STA. 21+00	33	8" COMPACTED
TOTAL	160 TON	

PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"

LOCATION	FOOT	REMARKS
F.E.R. STA. 20+87	44	
F.E.L. STA. 21+00	38	
TOTAL	82 FOOT	

SCHEDULE OF QUANTITIES - CONT.

PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"

LOCATION	FOOT	REMARKS
F.E.L. STA. 19+26	38	
TOTAL	38 FOOT	

PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND - SIZE 54"

LOCATION	FOOT	REMARKS
F.E.R. STA. 19+24	42	
TOTAL	42 FOOT	

STEEL END SECTIONS 18"

LOCATION	EACH	REMARKS
F.E.R. STA. 20+87	2	
F.E.L. STA. 21+00	2	
TOTAL	4 EACH	

STEEL END SECTIONS 24"

LOCATION	EACH	REMARKS
F.E.L. STA. 19+26	2	
TOTAL	2 EACH	

STEEL END SECTIONS, EQUIVALENT ROUND - SIZE 54"

LOCATION	EACH	REMARKS
F.E.R. STA. 19+24	2	
TOTAL	2 EACH	

PIPE UNDERDRAINS 6"

LOCATION	FOOT	REMARKS
LT. STA. 15+50 - 19+76	438	
RT. STA. 15+50 - 19+76	438	
LT. STA. 20+44 - 24+00	368	
RT. STA. 20+44 - 24+00	368	
TOTAL	1612 FOOT	

SCHEDULE OF QUANTITIES

TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	UNIT	REMARKS
LT. STA. 19+70	12	STUMP
LT. STA. 19+84	6	
LT. STA. 19+84	6	
TOTAL	24 UNIT	

TREE REMOVAL (OVER 15 UNITS DIAMETER)

LOCATION	UNIT	REMARKS
LT. STA. 20+24	16	
TOTAL	16 UNIT	

SEEDING, CLASS 3 (SPECIAL)

LOCATION	ACRE	REMARKS
RT. STA. 12+00 - 15+50	0.22	
RT. STA. 15+50 - 19+11	0.25	
LT. STA. 15+50 - 19+16	0.22	
RT. STA. 19+37 - 19+98	0.03	
LT. STA. 19+36 - 20+00	0.02	
RT. STA. 20+15 - 20+73	0.02	
LT. STA. 20+26 - 20+90	0.03	
RT. STA. 20+99 - 24+00	0.20	
LT. STA. 21+08 - 24+00	0.18	
TOTAL	1.17 ACRE	

FILE NAME = R:\Struct\115CDR\Drawings\115genched.dgn

WILLET, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
 809 East Second Street Dixon, IL 61021
 Phone 815.294.3381 Fax 815.294.3385
 Design Firm # 184-00918
 www.willett-hofmann.com

USER NAME =	DESIGNED - MAS	REVISED -
PLOT SCALE =	DRAWN - RDA	REVISED -
PLOT DATE =	CHECKED - BKC	REVISED -
	DATE - 06/09	REVISED -

BUREAU COUNTY
MINERAL ROAD DISTRICT
TR 257 (N. 1600 AVE.) OVER KING CREEK

GENERAL NOTES & SCHEDULES

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
257	07-17137-00-BR	BUREAU	27	3
			CONTRACT NO. 87381	
FED. ROAD DIST. NO. 7 (ILLINOIS) FED. AID PROJECT BR05-0011(071)				