





LEGEND

-  Perimeter Erosion Barrier
-  Seeding, Class 3 (Special)
-  Erosion Control Blanket
-  Temporary Ditch Checks

EROSION CONTROL NOTES

Silt Fence shall be installed at all locations where water drains away from the project and shall be completed prior to construction efforts. The Silt Fence will remain in place until the contributing area is stabilized.

Perimeter Erosion Barrier shall comply with Section 280 of the Standard Specifications and shall be placed as shown on the "Erosion Control Plan" and in accordance with stations shown on the "Schedule of Quantities" sheet or as directed by the engineer.

The soil erosion and sediment control practices will be inspected weekly and after 1/2" or more of rain by the individual on site in charge of soil erosion and sediment control during the construction of the project.

Erosion control blanket shall be installed at all disturbed areas with slopes equal to or greater than 1V:5H and in critical areas (i.e. detention basin perimeters, streambanks, berms, etc.) immediately upon final grading.

Stockpiles of soil and other building materials to remain in place more than three (3) days shall be furnished with erosion and sediment control measures (i.e. Perimeter Erosion Barrier). Stockpiles to remain in place for 30 days or more shall receive temporary seeding.

All adjacent streets must be kept clear of debris, inspected daily and cleaned when necessary.

Temporary ditch checks shall comply with Section 280 of the Standard Specifications for Road and Bridge Construction and Standard 280001-04 located in the Proposal. Temporary ditch checks shall be aggregate.

Temporary ditch checks shall be placed at 100' maximum centers and shall be placed at stations called out in the Schedule of Quantities or as directed by the engineer.

For Seeding, Class 3 (Special), see Special Provisions.

Erosion control blanket shall be placed in ditches as shown on this Erosion Control Plan Sheet and in accordance with Section 251 of the Standard Specifications for Road and Bridge Construction.

The use of green dye in the erosion control blanket is not acceptable.

The use of asphalt as a binder is not acceptable.

Mulch shall be placed over the entire seeded region.

Item	Unit	Quantity
Seeding, Class 3 (Special)	Acre	1.17
Erosion Control Blanket	Sq. Yd.	5,663
Temporary Ditch Checks	Each	16
Perimeter Erosion Barrier	Foot	80

FILE NAME = s:\stud\115CD\Drawing\115Erosion.dgn

WILLET, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
 809 East Second Street Dixon, IL 61021
 Phone 815.284.3381 Fax 815.284.3385
 Design Firm # 194-0018
 www.willetthofmann.com

USER NAME =	DESIGNED - MAS	REVISED -
PLOT SCALE =	DRAWN - RDA	REVISED -
PLOT DATE =	CHECKED - BKC	REVISED -
	DATE - 06/09	REVISED -

BUREAU COUNTY
MINERAL ROAD DISTRICT
TR 257 (N. 1600 AVE.) OVER KING CREEK

EROSION CONTROL PLAN

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
257	07-17137-00-BR	BUREAU	27	9
CONTRACT NO. 87381			FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT BROS-001(07)	