

SUMMARY OF QUANTITIES

Code #	Pay Item Description	Unit	Total Quantity	ARRA	NON-PARTICIPATING
20200100	EARTH EXCAVATION	CU YD	102		102
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	509		509
25000210	SEEDING, CLASS 2A	ACRE	0.1		0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9		9.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9		9.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9		9.0
25100630	EROSION CONTROL BLANKET	SQ YD	509		509
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	409		409
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	158	158	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	381	381	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,972	1,972	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,096	2,096	
40701891	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"	SQ YD	100		100
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14	14	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,685		3,685
44000100	PAVEMENT REMOVAL	SQ YD	100		100
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	3,839	3,839	
* 44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (SPECIAL)	FOOT	330	280	50
* 44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	2,000	2,000	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	309	309	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	79	79	
* 60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	34	34	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
67100100	MOBILIZATION	L SUM	1	1	
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,835	1,835	
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,468	1,468	
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	514	514	
Δ 78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,860	1,860	
* XX007729	DETECTABLE WARNINGS (SPECIAL)	SQ FT	368	368	
* XX008125	HEATER SCARIFICATION WITH REJUVINATING OIL, 1 1/4" (SPECIAL)	SQ YD	23,450	23,450	
* Special Provision					
Δ Specialty Item					
NOTE - CONSTRUCTION FUND TYPE CODE (1000)					

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - JAR	REVISED - DWS 6-29-2009	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	Summary of Quantities			F.A.J. RTE. 6470	SECTION 09-00037-00-R5	COUNTY KENDALL	TOTAL SHEETS 13	SHEET NO. 3
		DRAWN - DWS	REVISED - DWS 7-24-2009					CONTRACT NO. 87417				
		CHECKED -	REVISED -		SCALE:			SHEET NO. 3 OF 13 SHEETS STA. TO STA.				
		PLLOT SCALE = #SCALE#	DATE - 6-2-2009					ILLINOIS FED. AID PROJECT				