

W:\PROJECTS\DRAWINGS\MACOMB\WARD ST\PHASE 2\WARD-ST-PH2-QUANT-SCH.DWG, STM-SCHEDULE, 6/30/2009 10:35:58 AM

CITY OF MACOMB-WARD STREET
 SEC. 09-00139-01-PV F.A.U. 6919
 PROJ. ARA-5040 (010)
 CONTRACT No. 89527 SHT 6 OF 32

SHEET NO.
6
 of **32**

McClure
 Engineering Associates, Inc.
 Macomb, Illinois 61455
 74 East Jackson Street
 Macomb, Illinois 61455
 Design Firm License #184-000016 Copyright 2009 by McClure Engineering Associates, Inc.

STM No.	STR No. TO STR No.	% OF SLOPE	SS 1 RCP CL 4		SS 2 RCP CL 3		SS PVC SDR26 12 CLASS 160	MAN TA 5 DIA TIF OL	INL TA T3F&G	INL TA TBGRATE	RELOCATE INLET, SPL	INL SPL N1	CONCRETE COLLAR	TRENCH BACKFILL
			12"	21"	12"	21"								
62A	EXIST.-12A	1.00	7	---	---	---	---	---	---	---	---	1	---	1.5
63A	EXIST.-11A	0.44	6	---	---	---	---	---	---	---	---	1	1	1.8
64	F-E	0.28	---	120	---	---	---	1	---	---	---	---	---	36.4
65	E-10	0.44	9	---	---	---	---	---	---	---	---	1	---	2.3
66	E-9	0.44	30	---	---	---	---	---	---	---	---	1	---	7.7
67	E-D	0.21	---	---	---	156	---	1	---	---	---	---	---	55.8
68	D-8	0.44	10	---	---	---	---	---	---	---	---	1	---	2.6
69	D-7	0.44	30	---	---	---	---	---	---	---	---	1	---	7.7
70	D-C	0.21	---	---	---	111	---	1	---	---	---	---	---	76.1
71	C-5	0.44	30	---	---	---	---	---	---	---	---	1	---	7.1
72	C-6	0.44	---	---	---	---	24	---	1	---	---	---	---	5.7
73	C-B	0.21	---	---	---	141	---	1	---	---	---	---	---	107.2
74	B-3	0.44	30	---	---	---	---	---	---	---	---	1	---	19.0
74A	3A-3	0.50	13	---	---	---	---	---	---	1	---	---	---	3
75	B-4	0.44	10	---	---	---	---	---	---	---	---	1	---	6.3
76	B-2A	0.44	---	---	---	---	54	---	---	---	1	---	---	---
77	B-A	0.21	---	---	---	116	---	1	---	---	---	---	---	102.0
78	A-2	0.44	---	---	---	29	---	---	---	---	---	1	---	9.3
79	A-1	0.44	---	---	---	9	---	---	---	---	---	1	---	2.9
80	A-A1	0.21	---	---	---	107	---	1	---	---	---	---	---	110.5
TOTAL			175	120	38	631	78	6	1	1	1	11	1	564.9

WATER SERVICE REPLACEMENT SCHEDULE				
LOCATION	WATER SERVICE CONNECTION	3/4" COPPER WATER SERVICE	2" PVC CASING PIPE	TRENCH BACKFILL
STA 329+57	1	47	22	15.4
STA 329+93	1	47	22	15.4
STA 330+76	1	66	22	16.6
STA 330+79	1	67	22	16.6
STA 331+49	1	48	22	15.4
STA 332+43	1	50	22	17.8
STA 332+96	1	50	22	17.8
STA 333+31	1	51	22	18.5
STA 333+99	1	47	22	15.1
STA 334+69	1	60	22	17.8
TOTAL	10	533	220	149.8

DOMESTIC METER VAULTS TO BE MOVED	
LOCATION	EACH
25' LT STA 330+69	1
25' LT STA 330+71	1
TOTAL	2

DOMESTIC WATER SERVICE BOXES TO BE MOVED	
LOCATION	EACH
24' LT STA 330+69	1
24' LT STA 330+71	1
TOTAL	2

DOMESTIC METER VAULTS TO BE ADJUSTED	
LOCATION	EACH
22' LT STA 329+56	1
23' LT STA 331+49	1
24' LT STA 332+41	1
24' LT STA 332+95	1
24' LT STA 333+30	1
30' RT STA 333+70	1
31' RT STA 333+73	1
30' RT STA 333+86	1
22' LT STA 333+99	1
32' LT STA 334+68	1
TOTAL	10

DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	
LOCATION	EACH
22' LT STA 329+92	1
22' LT STA 331+47	1
TOTAL	2

FIRE HYDRANTS TO BE MOVED		
EXISTING	PROPOSED	EACH
24.0' RT STA 336+33.7 TO 20.7' RT STA 336+31.7		1
TOTAL		1

WATER VALVES TO BE ADJUSTED	
LOCATION	EACH
30' RT STA 332+39	1
29' RT STA 332+80	1
TOTAL	2

PLOTTING SCALE: 1" = 1'
 DRAWN BY: JAH
 CHECKED BY: JAR
 DATE: MARCH 2009

NO.	REVISIONS	DATE

WARD STREET IMPROVEMENTS - PHASE 2
SCHEDULE OF QUANTITIES
 CITY OF MACOMB
 SOUTH WARD ST.
 FILE NAME: \\MACOMB\WARD\PHASE 2\WARD-ST-PH2-QUANT-SOL.DWG FIELD BOOK No. 2257 JOB NUMBER: 02-29-08099
 MACOMB, ILLINOIS