

SUMMARY OF QUANTITIES

VERMILION COUNTY
 RURAL
 MULTILANE
 100% STATE
 MINOR
 STRUCTURE
 REPAIR
I-74
 SFTY-2A
 S.N. 092-0003
 S.N. 092-0004

CODE NO	ITEM	UNIT	TOTAL QUANTITY
A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5.0
A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5.0
A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5.0
20100500	TREE REMOVAL, ACRES	ACRE	0.3
20300100	CHANNEL EXCAVATION	CU YD	2453.0
25000310	SEEDING, CLASS 4	ACRE	0.3
25100115	MULCH, METHOD 2	ACRE	0.3
28100713	STONE DUMPED RIPRAP, CLASS A7	SQ YD	4008.0
44000300	CURB REMOVAL	FOOT	100.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	111.1
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	111.1
48301000	PROTECTIVE COAT	SQ YD	111.1
63300205	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	100.0
66201120	CONCRETE SHOULDER CURB	FOOT	100.0
66500105	WOVEN WIRE FENCE, 4'	FOOT	84.0
66501600	WOVEN WIRE GATES, 4' X 16' DOUBLE	EACH	1.0
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	100.0
67100100	MOBILIZATION	L SUM	1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.0

NO SPECIALTY ITEMS

*D-5 SCOUR MITIGATION 2009-1

FILE NAME : c:\ph_work\p1\dot\simsgm\d0117763\90945	USER NAME = simsgm cover.dgn	DESIGNED - BH	REVISED - JDC - 4/30/09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 40.0000' / IN.	DRAWN - JP	REVISED -			VAR.	*	VERMILION	12	4
	PLOT DATE = 6/30/2009	CHECKED -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	CONTRACT NO. 90945		
		DATE - 01-22-2008	REVISED -				TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT