

GENERAL NOTES

- THE ENGINEER SHALL NOT GUARANTEE THE WORK OF ANY CONTRACTOR OR SUBCONTRACTOR, SHALL HAVE NO AUTHORITY TO STOP WORK, SHALL HAVE NO SUPERVISION OR CONTROL AS TO THE WORK OR PERSONS DOING THE WORK, SHALL NOT BE RESPONSIBLE FOR SAFETY IN, ON, OR ABOUT THE JOB SITE OR HAVE ANY CONTROL OF THE SAFETY OR ADEQUACY OF ANY EQUIPMENT, BUILDING COMPONENT, SCAFFOLDING, SUPPORTS, FORMS OR OTHER WORK AIDS, AND SHALL HAVE NO DUTIES OR RESPONSIBILITIES IMPOSED BY ACTS GOVERNING THE WORKPLACE. IN ADDITION, THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION SHALL BE MODIFIED AS FOLLOWS:  
  
UNDER ARTICLE 105.01, ADD THE FOLLOWING SENTENCE: NOTHING CONTAINED HEREIN SHALL RELIEVE THE CONTRACTOR OF HIS/HER DUTY TO OBSERVE AND COMPLY WITH ALL APPLICABLE LAWS, NOR SHALL THE ENGINEER BE RESPONSIBLE FOR THE CONTRACTOR'S COMPLIANCE OR NON-COMPLIANCE WITH SUCH LAWS.  
UNDER ARTICLE 107.1, ADD THE FOLLOWING SENTENCE: THE ENGINEER SHALL NOT BE RESPONSIBLE FOR THE CONTRACTOR'S DUTY TO OBSERVE AND COMPLY WITH THE PROVISIONS OF THIS SECTION, OR FOR THE CONTRACTOR'S FAILURE TO DO SO.
- THE CONTRACTOR AGREES THAT HE/SHE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS, DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT. THIS INCLUDES SAFETY OF ALL PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE COUNTY AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT.
- ALL ELEVATIONS ARE BASED ON U.S.G.S. MEAN SEA-LEVEL DATUM. THE PROPOSED GRADE ELEVATIONS SHOWN ON THE DRAWINGS ARE FINISH ELEVATIONS, AT LOCATIONS AS INDICATED.
- THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES WERE OBTAINED FROM RECORDS AND FIELD SURVEYS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UNDERGROUND UTILITY LOCATIONS PRIOR TO EXCAVATION FOR THE NEW WORK.
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 1-800-892-0123 FOR FIELD LOCATIONS FOR BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED). THE CITY OF DECATUR SHALL BE CONTACTED FOR FIELD LOCATIONS OF WATER MAIN AND SANITARY SEWER.
- THE CONTRACTOR SHALL COORDINATE HIS/HER CONSTRUCTION ACTIVITIES WITH AFFECTED UTILITY COMPANIES.
- THE ABBREVIATION SSRB SHALL REFER TO THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION ADOPTED JANUARY 1, 2007.

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY	ITEP	COUNTY HIGHWAY FUNDS
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5		0.5
25101504	WOOD CHIP MULCH 4"	SQ YD	100	100	
28000500	INLET AND PIPE PROTECTION	EACH	30		30
67100100	MOBILIZATION	L SUM	1	1	
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
Z0010555	DITCH CLEANING	FOOT	2750		2750
Z0010605	CLEANING DRAINAGE SYSTEM	L SUM	1		1
XX008094	TREES, GROUP 1	L SUM	1	1	
XX008095	TREES, GROUP 2	L SUM	1	1	
XX008096	SHRUBS, GROUP 1	L SUM	1	1	
XX008097	SHRUBS, GROUP 2	L SUM	1	1	
XX008098	GRASSES, GROUP 1	L SUM	1	1	
XX008099	FORBS, GROUP 1		1	1	
XX008100	FERTILIZER TABLETS	EACH	1128	1128	

BENCHMARK

BM 5002-2  
CHISELED SQUARE ON EAST SIDE ON TOP OF LIGHT POLE FOUNDATION ON SE CORNER OF USDA PARKING LOT.  
ELEVATION 687.07

BM 4604-17  
CHISELED SQUARE ON NW CORNER MAST ARM FOUNDATION AT SW QUADRANT OF THE INTERSECTION OF MOUND ROAD AND BRUSH COLLEGE ROAD.  
ELEVATION 682.31

REVISIONS			DRAWN BY DATE	
No.	DATE	INITIALS	DLB	2/09
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				

PROGRESS CITY MACON COUNTY, ILLINOIS		DECATUR CHICAGO (317) 423-8544 (773) 714-0050
<b>HOMER L. CHASTAIN &amp; ASSOCIATES, LLP</b> CONSULTING ENGINEERS 184-001377		ROCKFORD (815) 489-0050
CHECKED BY DATE PPW 2/09	BOOK NUMBER 478	PROJECT No. 5248
		SHEET No. 2