

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	JACKSON	67	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*12-1B-1d9 BSMART FY 10-1				

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	LENGTH (FOR INFORMATION ONLY) FEET	PAVEMENT MARKING REMOVAL SQ FT	TEMPORARY PAVEMENT MARKING LINE - 4"		PAINT PAVEMENT MARKING - LINE 4"		WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH
			WHITE FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT			
FAP RT. 331 (IL 13)									
235+00 TO 251+00	1460						973.3		
235+00 TO 238+00	300	100.0	375.0	300.0	375.0	300.0	225.0		
239+50 TO 242+50	300	100.0	375.0	300.0	375.0	300.0	225.0		
240+50 TO 247+25	675		843.8	675.0	843.8	675.0	506.2	5.0	5.0
244+50 TO 247+00	250	83.3	312.5	250.0	312.5	250.0	187.5		
248+00 TO 251+00	300	100.0	375.0	300.0	375.0	300.0	225.0		
TOTALS		383	2281	1825	2281	1825	2342	5	5
			4106		4106				

PLOT DATE = 3/18/2009
 FILE NAME = c:\pawork\pawork\shp\par-dgt\shp\43645\43655801.dgn
 PLOT NAME = shp\par-dgt\shp\43645\43655801.dgn
 USER NAME = shp\par-dgt