

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY 100% STATE	CONSTRUCTION CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY I000	BRIDGE X081-2A
20200100	EARTH EXCAVATION	CU YD	541	541	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	480	480	
35800100	PREPARATION OF BASE	SQ YD	85	85	
35800200	AGGREGATE BASE REPAIR	TON	10	10	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	460	460	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	400	400	
44000100	PAVEMENT REMOVAL	SQ YD	120	120	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	70	70	
44000700	APPROACH SLAB REMOVAL	SQ YD	725	725	
44004250	PAVED SHOULDER REMOVAL	SQ YD	125	125	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	445	445	
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	85	85	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	6.1	6.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.9	15.9	
50300260	BRIDGE DECK GROOVING	SQ YD	263	263	
50300300	PROTECTIVE COAT	SQ YD	321	321	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	300	300	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2,468	2,468	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8,170	8,170	
50800515	BAR SPLICERS	EACH	43	43	
51500100	NAME PLATES	EACH	1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	113	113	
60500060	REMOVING INLETS	EACH	2	2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	60	60	
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	2	2	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	642	642	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	953	953	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	4
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.2	0.8

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY 100% STATE	CONSTRUCTION CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY I000	BRIDGE X081-2A
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,650	5,650	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	430	430	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350	350	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	40	40	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,700	13,700	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	155	155	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	90	90	
* 78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	SQ FT	40	40	
* 78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	440	440	
* 78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	155	155	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	405	405	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	27	27	
* 78200450	MONODIRECTIONAL GUARDRAIL REFLECTORS	EACH	14	14	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	31	31	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5,100	5,100	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	410	410	
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	200	200	
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	60	60	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	200	200	
* 87301305	ELECTRICAL CABLE IN CONDUIT, LEAD-IN, 14# PAIR	FOOT	450	450	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	545	545	
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	354		354
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	16,500	16,500	
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	60	60	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	17		17
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.8
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

* DENOTES SPECIALTY ITEM

FILE NAME = N:\PROJ\3325\3325_24\Design\ProposedPlan\3325_24-43-mcd.dgn



Ciiorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60655
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = wlonaster	DESIGNED - JCC	REVISED -
	DRAWN - JCC	REVISED -
PLOT SCALE = 1/8" = 1' IN.	CHECKED - MJL	REVISED -
PLOT DATE = 7/8/2008	DATE - 07/09/2008	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU 0318/US ROUTE 6 (RAILROAD AVENUE)
OVER I & M CANAL
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 0318	SECTION DB-1-R-B	COUNTY WILL	TOTAL SHEETS 40	SHEET NO. 3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D88	

Rev