

SUMMARY OF QUANTITIES

UABAH

| CODE NO.            | ITEMS                                                         | UNIT           | TOTAL QUANTITY | 90% FEDERAL - 10% STATE |         |         |         |      |
|---------------------|---------------------------------------------------------------|----------------|----------------|-------------------------|---------|---------|---------|------|
|                     |                                                               |                |                | 1000-2A                 | J000-2A | Y031-1F | X271-2A | Y007 |
| <del>40603340</del> | <del>HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70</del>       | <del>TON</del> | <del>217</del> | <del>217</del>          |         |         |         |      |
| 40603595            | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90      | TON            | 354            | 354                     |         |         |         |      |
| 42000521            | PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)               | SO YD          | 14,340         |                         | 14,340  |         |         |      |
| 42001300            | PROTECTIVE COAT                                               | SO YD          | 18,100         | 18,100                  |         |         |         |      |
| 42001400            | BRIDGE APPROACH PAVEMENT (SPECIAL)                            | SO YD          | 470            |                         |         | 470     |         |      |
| 42100320            | CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11" | SO YD          | 1401           | 1401                    |         |         |         |      |
| 42100920            | PAVEMENT REINFORCEMENT 11"                                    | SO YD          | 1401           | 1401                    |         |         |         |      |
| 42300400            | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH            | SO YD          | 95             |                         | 95      |         |         |      |
| 44000100            | PAVEMENT REMOVAL                                              | SO YD          | 17,948         |                         | 17,948  |         |         |      |
| 44000153            | HOT-MIX ASPHALT SURFACE REMOVAL, 1"                           | SO YD          | 2362           | 2362                    |         |         |         |      |
| 44000160            | HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"                       | SO YD          | 1641           | 1641                    |         |         |         |      |
| 44000200            | DRIVEWAY PAVEMENT REMOVAL                                     | SO YD          | 1168           |                         | 1168    |         |         |      |
| 44000500            | COMBINATION CURB AND GUTTER REMOVAL                           | FOOT           | 1685           | 855                     | 830     |         |         |      |
| 44004000            | PAVED DITCH REMOVAL                                           | FOOT           | 357            |                         | 357     |         |         |      |
| 44004250            | PAVED SHOULDER REMOVAL                                        | SO YD          | 5022           |                         | 5022    |         |         |      |
| 44201325            | CLASS C PATCHES, TYPE I, 8 INCH                               | SO YD          | 15             | 15                      |         |         |         |      |
| 44201329            | CLASS C PATCHES, TYPE II, 8 INCH                              | SO YD          | 10             | 10                      |         |         |         |      |
| 44201333            | CLASS C PATCHES, TYPE III, 8 INCH                             | SO YD          | 15             | 15                      |         |         |         |      |
| 48101500            | AGGREGATE SHOULDERS, TYPE B 6"                                | SO YD          | 1149           | 1149                    |         |         |         |      |
| 48203029            | HOT-MIX ASPHALT SHOULDERS, 8"                                 | SO YD          | 1168           | 1168                    |         |         |         |      |
| 48300600            | PORTLAND CEMENT CONCRETE SHOULDERS 11"                        | SO YD          | 1275           |                         | 1275    |         |         |      |
| 48301000            | PROTECTIVE COAT                                               | SO YD          | 1275           |                         | 1275    |         |         |      |
| 50100100            | REMOVAL OF EXISTING STRUCTURES                                | EACH           | 1              |                         |         | 1       |         |      |
| 50104400            | CONCRETE HEADWALL REMOVAL                                     | EACH           | 7              |                         | 7       |         |         |      |
| 50104600            | CONCRETE RETAINING WALL REMOVAL                               | FOOT           | 83             |                         |         |         | 83      |      |
| 50157300            | PROTECTIVE SHIELD                                             | SO YD          | 510            |                         |         | 510     |         |      |
| 50200100            | STRUCTURE EXCAVATION                                          | CU YD          | 188            |                         |         | 153     | 35      |      |
| 50300100            | FLOOR DRAINS                                                  | EACH           | 12             |                         |         | 12      |         |      |
| 50300225            | CONCRETE STRUCTURES                                           | CU YD          | 249.1          |                         |         | 216.3   | 32.8    |      |
| 50300255            | CONCRETE SUPERSTRUCTURE                                       | CU YD          | 609.6          |                         |         | 609.6   |         |      |
| 50300260            | BRIDGE DECK GROOVING                                          | SO YD          | 1559           |                         |         | 1559    |         |      |
| 50300280            | CONCRETE ENCASEMENT                                           | CU YD          | 8.0            |                         |         | 8.0     |         |      |
| 50300300            | PROTECTIVE COAT                                               | SO YD          | 2286           |                         |         | 2130    | 156     |      |
| 50500105            | FURNISHING AND ERECTING STRUCTURAL STEEL                      | L SUM          | 1              |                         |         | 1       |         |      |
| 50500505            | STUD SHEAR CONNECTORS                                         | EACH           | 7008           |                         |         | 6864    | 144     |      |
| 50700209            | UNTREATED TIMBER LAGGING                                      | SO FT          | 511            |                         |         |         | 511     |      |
| 50800205            | REINFORCEMENT BARS, EPOXY COATED                              | POUND          | 170,340        |                         |         | 165,760 | 4580    |      |
| 50800515            | BAR SPLICERS                                                  | EACH           | 2049           |                         |         | 2049    |         |      |
| 50900105            | ALUMINUM RAILING, TYPE L                                      | FOOT           | 203            |                         |         | 203     |         |      |

|                         |          |                  |              |           |
|-------------------------|----------|------------------|--------------|-----------|
| F.A.I. RTE.             | SECTION  | COUNTY           | TOTAL SHEETS | SHEET NO. |
| 57                      |          | WILL             | 303          | 5         |
| STA.                    | TO STA.  |                  |              |           |
| FED. ROAD DIST. NO.     | ILLINOIS | FED. AID PROJECT |              |           |
| *991821 R-389-1B-1-BR-2 |          | CONTRACT: 62253  |              |           |

- SPECIALTY ITEM
- 50% OF THE AS-BUILT QUANTITY WILL BE CHARGED TO AQUA ILLINOIS (PRIVATE UTILITY BENEFIT). FUND CODE: Y060 (50% AQUA/50% STATE)
- + NON-PARTICIPATING ITEM
- ++ NON-PARTICIPATING FOR RETROREFLECTIVE SIGN SHEETING ONLY - 100% STATE
- \* NON-PARTICIPATING ITEM - 100% MONEE FIRE PROTECTION DISTRICT. FUND CODE: Y031-3D

DESIGN FIRM REGISTRATION No. 184-000450  
**Clark Metz** ENGINEERS  
 118 SOUTH CLINTON STREET SUITE 600  
 CHICAGO, IL 60681  
 PHONE : 312.648.9900 FAX : 312.648.0204

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 I-57 AT MANHATTAN - MONEE ROAD  
 SUMMARY OF QUANTITIES  
 2 OF 9  
 SCALE: VERT. NTS  
 HORIZ. NTS  
 DATE 8/1/2008  
 DRAWN BY KLM  
 CHECKED BY TMW

02231 0002  
 07/23/08 6/10/2008