


SUMMARY OF QUANTITIES

URBAN

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	WILL	303	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*991A2) R-3A9-1B-1-BR-2		CONTRACT: 62253		

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	90% FEDERAL - 10% STATE				
				I000-2A	J000-2A	Y031-1F	X271-2A	Y007
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	20	20				
* A2006814	TREE, QUERCUS MUEHLENBERGII (CHINKAPIN OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	20	20				
* A2007114	TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	20	20				
* A2C010G3	TREE, ASIMINA TRILOBA (PAW PAW), CONTAINER GROWN, 3-GALLON	EACH	10	10				
* B2001164	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	50	50				
* B2002216	TREE, CRATAEGUS VIRDIS WINTER KING (WINTER KING GREEN HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	50	50				
* C2C02024	SHRUB, CORYLUS AMERICANA (AMERICAN FILBERT), 2' HEIGHT, CONTAINER	EACH	100	100				
* C2C11736	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, CONTAINER	EACH	100	100				
* E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	100	100				
* K0036120	MULCH PLACEMENT 4"	SO YD	3952	3952				
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	85			85		
X0325734	SLOTTED DRAIN REMOVAL	FOOT	36		36			
X0325864	BRIDGE APPROACH PAVEMENT REMOVAL	SO YD	277		277			
** X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	12		12			
** X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	56		56			
** X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	90		90			
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	100	100				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	616	616				
X0322323	WEED CONTROL, TEASEL	GALLON	1	1				
X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	36	36				
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1143		1143			
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	14		14			
* X0323670	PREFORMED DETECTOR LOOP	FOOT	1136		1136			
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	6413		6413			
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	12,826		12,826			
* X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1		1			
* X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	91		91			
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	644				644	
* X0325047	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE-RHW) 3-1/C NO. 2 AND 1/C NO. 4 GROUND	FOOT	470		470			
X0712400	TEMPORARY PAVEMENT	SO YD	4312	4312				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	5				
X4023000	TEMPORARY ACCESS (ROAD)	EACH	3	3				
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	1	1				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	435	435				
* X5120902	FURNISHING SOLDIER PILES HP 14X73	FOOT	247				247	
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	1159		1159			

- * SPECIALTY ITEM
- ** 50% OF THE AS-BUILT QUANTITY WILL BE CHARGED TO AQUA ILLINOIS (PRIVATE UTILITY BENEFIT). FUND CODE: Y060 (50% AQUA / 50% STATE)
- + NON-PARTICIPATING ITEM
- ++ NON-PARTICIPATING FOR RETROREFLECTIVE SIGN SHEETING ONLY - 100% STATE
- * NON-PARTICIPATING ITEM - 100% MONEE FIRE PROTECTION DISTRICT. FUND CODE: Y031-3D



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 I-57 AT MANHATTAN - MONEE ROAD
 SUMMARY OF QUANTITIES
 8 OF 9

SCALE: VERT. NTS
 HORIZ. NTS
 DATE 8/1/2008

DRAWN BY KLM
 CHECKED BY TMW

02231 0288.
 6/18/2008

Rev.