

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	WILL	303	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
+9911&21 R-3&9-11B-1-BR-2		CONTRACT: 62253		

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24					FOOT
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14029+26 LT		14029+50 LT	28	
	14029+50 LT		14032+12 LT	279	
	14030+58 RT		14032+66 RT	241	
	14032+60 LT		14035+46 LT	309	
	14033+17 RT		14036+31 RT	366	
	14038+53 RT		14042+09 RT	380	
	14039+80 LT		14041+52 LT	224	
TOTAL				1,827	

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12					FOOT
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14035+46 LT		14036+40 LT	94	
	14038+52 LT		14039+80 LT	128	
TOTAL				222	

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT					SQ YD
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14050+52		14050+82	142	
HAMILTON					
				71	
TOTAL				213	

STEEL PLATE BEAM GUARD RAIL, TYPE A						FOOT
LOCATION	STATION	OFFSET (FT)	TO	STATION	OFFSET (FT)	QUANTITY
MANHATTAN-						
MONEE ROAD	14026+53	23.28 LT		14028+53	30.49 LT	200
	14028+14	25.67 RT		14030+32	82 RT	250
	14038+63	37 RT		418+36	30 LT	225
	14038+96	43.46 LT		301+51	25.18 LT	312.5
RAMP A						
	101+29	8 RT		14030+58	82 RT	300
	101+90	22.18 LT		14035+92	37 RT	375
RAMP B						
	233+50	10.6 RT		14029+46	33.94 LT	625
	235+46	30 LT		14036+26	43 LT	525
RAMP D						
	418+13	18 RT		418+25	18 RT	12.5
TOTAL						2,825

DRIVEWAY PAVEMENT REMOVAL			SQ YD
LOCATION	STATION	QUANTITY	
MANHATTAN-			
MONEE ROAD	14025+89 RT	103	
	14029+17 LT	398	
	14043+83 RT	133	
	14043+98 LT	142	
	14045+33 RT	122	
	14045+34 LT	114	
	14047+13 RT	156	
TOTAL		1168	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12					FOOT
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14033+52 RT		14036+32 RT	281	
	14033+52 RT		14036+32 RT	281	
	14038+55 LT		14041+17 LT	262	
	14038+55 LT		14041+17 LT	262	
	14042+23 LT		14044+50 LT	227	
	14042+23 LT		14044+50 LT	228	
	14044+50 LT		14045+58 LT	108	
	14044+50 LT		14045+58 LT	108	
TOTAL				1757	

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12					FOOT
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14026+58 LT		14029+50 LT	292	
	14026+58 RT		14029+50 RT	292	
	14029+50 LT		14032+37 LT	288	
	14029+50 RT		14032+37 RT	287	
TOTAL				1159	

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"			SQ YD
LOCATION	STATION	QUANTITY	
MANHATTAN-			
MONEE ROAD	14047+13	95	
TOTAL			95

AGGREGATE SUBGRADE					CU YD
LOCATION	STATION	TO	STATION	DEPTH	QUANTITY
MANHATTAN-					
MONEE ROAD	14024+23.67 LT		14027+47 RT	12"	228
	14024+23.67 RT		14027+47 LT	12"	197
	14027+47 RT		14029+50	12"	152
	14027+47 LT		14029+50	12"	192
	14029+50		14036+35	12"	1756
	14038+53		14044+50	12"	1492
	14044+50		14046+65	12"	599
RAMP A					
	101+00		102+00	12"	270
RAMP B					
	200+00		215+00	14.25"	1192
	215+00		224+81	14.25"	586
	230+00		237+27	12"	649
RAMP C					
	301+00		303+00	12"	340
RAMP D					
	415+60		418+50	12"	584
TOTAL					8237

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18					FOOT
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14042+04 LT		14044+50 LT	261	
	14042+57 RT		14044+50 RT	122	
	14044+50 LT		14046+87 LT	277	
	14044+50 RT		14045+76 RT	137	
	14046+05 RT		14050+82 RT	487	
	14047+33 LT		14050+82 LT	398	
TOTAL				1,682	

CONCRETE MEDIAN SURFACE, 6 INCH					SQ FT
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14026+50		14032+37	8518	
	14032+50		14036+32	759	
	14038+55		14042+23	700	
	14044+60		14045+58	353	
TOTAL				10330	

SUB-BASE GRANULAR MATERIAL, TYPE B, 4"				SQ YD
LOCATION	STATION	TO	STATION	QUANTITY
MANHATTAN-				
MONEE ROAD	14046+65 LT		14050+82 LT	107
	14046+65 RT		14050+82 RT	410
TOTAL				517

TEMPORARY PAVEMENT					SQ YD
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	STAGE I				
	14019+55 RT		14030+24 RT	1361	
	14030+80 RT		14032+43 RT	69	
	14033+25 RT		14036+24 RT	247	
	14038+53 RT		14042+23 RT	971	
	14042+39 RT		14045+28 RT	306	
STAGE IIA					
	14029+64 LT		14031+93 LT	138	
	14032+56 LT		14036+35 LT	581	
	14038+82 LT		14041+59 LT	213	
	14042+13 LT		14045+67 LT	259	
	14046+68 LT		14046+89 LT	16	
	14047+30 LT		14049+00 LT	43	
STAGE IIB					
	14035+08 LT		14036+08 LT	44	
	106+28 LT		108+09 LT	64	
TOTAL				4312	

PORTLAND CEMENT CONCRETE BASE COURSE, 12"					SQ YD
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14046+65 LT		14050+82 LT	37	
	14046+65 RT		14050+82 RT	268	
TOTAL				305	

HOT-MIX ASPHALT BASE COURSE, 8"					SQ YD
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14025+89 RT			83	
	14025+90 LT			34	
	14029+17 LT			218	
	14043+83 RT			78	
	14043+98 LT			84	
	14045+33 RT			68	
	14045+34 LT			58	
TOTAL				623	

STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"					SQ YD
LOCATION	STATION	TO	STATION	QUANTITY	
RAMP A					
	100+51		102+42	617	
RAMP B					
	223+60		237+27	1513	
RAMP C					
	300+50		303+06	647	
RAMP D					
	415+60		418+90	1382	
TOTAL				4159	

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT					SQ YD
LOCATION	STATION	TO	STATION	QUANTITY	
MANHATTAN-					
MONEE ROAD	14025+89 RT			83	
	14025+90 LT			34	
	14029+17 LT			218	
	14043+83 RT			78	
	14043+98 LT			84	
	14045+33 RT			68	
	14045+34 LT			58	
TOTAL				623	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 I-57 AT MANHATTAN - MONEE ROAD
 SCHEDULE OF QUANTITIES
 3 OF 3

SCALE: VERT. NTS
 HORIZ. NTS
 DATE 9/19/2008
 DRAWN BY BDC
 CHECKED BY TMW

