

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 63024				

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE	STP/TCM	BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT	STP	NON-PARTICIPATING	STP
FUNDING	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	
XX005963	ANTI-GRAFFITI COATING	SQ FT	25488		12197	1834	11457						
XX00598	ADDITIONAL GROUND ROD INSTALLATION	EACH	20									20 E	
XX006602	SHRUB, ARONIA MELANOCARPA 'MORTON' (IROQUOIS BEAUTY BLACK CHOKEBERRY), 2.5' HEIGHT, BALLED AND BURLAPPED	EACH	84	84									
XX006223	PERIMETER EROSION BARRIER, MODIFIED	FOOT	2620	2620									
XX006257	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	875	875									
XX006444	MULCH SPECIAL	ACRE	0.75									0.75 E	
XX8620020	UNINTERRUPTABLE POWER SUPPLY	EACH	2					1	1				
XX006629	SHRUB, RHUS TYPHINA BAILTIGER (TIGER EYE SUMAC), CONTAINER GROWN, 5-GALLON	EACH	94	94									
XX004238	BITUMINOUS DRIVE WAY REMOVAL AND REPLACEMENT	SQ YD	90									90 E	
XX007053	CONDUIT RISER ASSEMBLY 6"	EACH	1									1 E	
XX007054	HANDHOLE -DEH5	EACH	2									2 E	
XX007055	HANDHOLE -DEH6	EACH	1									1 E	
XX007138	2 WAY--2 3"PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	970									970 E	
XX007140	2 WAY--2- 5"PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	20									20 E	
XX007141	2 WAY--2- 6"PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	90									90 E	
XX172700	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10									
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	25	25									
X0301576	COAXIAL CABLE IN CONDUIT	FOOT	155					155					
X0320873	VIDEO VEHICLE DETECTOR	EACH	1					1					
X0321598	MANHOLES, TYPE A, 6'-DIAMETER, 2-TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	5	5									
X0322102	TEMPORARY SIDEWALK RAMPS	EACH	17	14								3 E	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	2344	2344									
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	240	240									
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	617	267								350 E	
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14-1C	FOOT	7864							7864			
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	10			10							
X0323199	SANITARY SEWER, DUCTILE IRON 10"	FOOT	560									560 W	
X0323330	PRECAST CONCRETE SUBSTRUCTURE	L SUM	1		1								

LEGEND:


- SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE
ADDENDUM 1	08/28/08

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 14 OF 19

CONSULTANT
TYLININTERNATIONAL

City of  **Naperville**

DRAWN: _____ SHEET NO. _____

CHECKED: _____

APPROVED: _____

DATE: APRIL 11, 2008

SCALE: NONE

JOB NO.: P-91-494-00 PROJECT NO.: M-CMM-7003 (985)

3:25 PM