

NOTES:


1. PROVIDE NEW LIGHT POLE AND ASSOCIATED LUMINAIRE PER NEW WORK REQUIREMENT. REFER TO GENERAL NOTES AND SYMBOLS SHEET FOR POLE AND LUMINAIRE INFORMATIONS.
2. EXISTING RELOCATED LIGHT POLES (R15 AND R16) SHALL BE CONNECTED TO NEW LIGHTING CONTROLLER "A3" AS INDICATED ON PROPOSED ELECTRICAL PLAN SHEET 2 OF 7.
3. PROVIDE NEW LIGHTING POLE AND LUMINAIRE PER NEW WORK REQUIREMENT. PROVIDE NEW WIRES AND CONNECT TO NEW LIGHTING CONTROLLER "A3", AS INDICATED ON ON PROPOSED ELECTRICAL PLAN SHEET 2 OF 7.
4. REFER TO PROPOSED ELECTRICAL PLAN SHEET 6 OF 7 FOR INFORMATION.
5. PROVIDE NEW CIRCUIT WIRES (3-1/C NO. 6 AWG, 1/C NO.6 AWG GROUND) WITHIN 2" DIAMETER UNIT DUCT.
6. PROVIDE NEW COMBINATION POLE WITH TRAFFIC SIGNAL MAST ARM AND LUMINAIRE. COORDINATE EXACT REQUIREMENTS WITH CITY OF NAPERVILLE.
7. EXISTING RELOCATED AND NEW LIGHT POLES SHALL BE FED FROM NEW CONTROLLER "A1", AS INDICATED ON PROPOSED ELECTRICAL PLAN SHEET 4 OF 7.
8. UNIT DUCT ENTERS CONDUIT EMBEDDED IN STRUCTURE. REFER TO STRUCTURAL PLANS.
9. PROVIDE 3/4" RGS CONDUIT WITH 2- 1/C NO. 10 AWG, 1- 1/C NO. 10 AWG GROUND FOR PEDESTRIAN WALKWAY LIGHTING CIRCUIT. CONNECT TO NEW CONTROLLER "A3", AS INDICATED ON PROPOSED ELECTRICAL PLAN SHEET 2 OF 7. ROUTE CONDUIT ALONG WITH STREET LIGHTING CIRCUIT ROUTE.
10. PROVIDE STAINLESS STEEL JUNCTION BOX (12"x12"x6") WITH WATERTIGHT SEAL CONNECTIONS FOR PEDESTRIAN BUDGET LIGHTING CIRCUIT.
11. PROVIDE STAINLESS STEEL JUNCTION BOX (12"x12"x6") WITH WATERTIGHT SEAL CONNECTIONS FOR PEDESTRIAN TUNNEL LIGHTING CIRCUIT.

REVISIONS	
NAME	DATE
ADDENDUM 1 - NEW SHEET	8/28/08



INTERSECTION IMPROVEMENT
 WASHINGTON STREET - 75th STREET
 PROPOSED ELECTRICAL PLAN
 WASHINGTON STREET
 SHEET 3 OF 7
 STA. 548+50 TO STA. 561+50

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN: JRH
 CHECKED: FO
 APPROVED: DEM
 DATE: 04/11/08
 SCALE: 1"=50'-0"
 JOB NO: P-91-494-00
 SHEET NO.
 PROJECT NO: CMM-7003 (983)