

SUMMARY OF QUANTITIES

IDC CODE NO	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE TIL TIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE	STP/TCM	BRIDGE	NOR:HEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT	STP	NON-PARTICIPATING	STP
FUNDING	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP	STP		
• 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1473	1173								300 E	
• 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1295	1295									
20101000	TEMPORARY FENCE	FOOT	7235	4835								2400 E	
• 20101200	TREE ROOT PRUNING	EACH	40									40 E	
20200100	EARTH EXCAVATION	CU YD	39935	38487	1448								
20200200	ROCK EXCAVATION	CU YD	596		346							250 E	
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	1220									1220 E	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5909	5434	166		309						
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	890			510	380						
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3903	3903									
20800150	TRENCH BACKFILL	CU YD	7026	6015								1011 W	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	11709	11709									
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	26120	25930								190 "	
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	15703	15703									
21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	10200	10200									
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	20	20									
• 25000210	SEEDING, CLASS 2A	ACRE	7	7									
• 25000310	SEEDING, CLASS 4	ACRE	2	2									
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	447	432								15 W	
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	447	432								15 W	
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	447	432								15 W	
• 25000920	SEEDING CLASS 1A (SPECIAL)	ACRE	1									1 E	
25100630	EROSION CONTROL BLANKET	SQ YD	92646	92646									
• 25200100	SODDING	SQ YD	190									190 W	
• 25200700	SODDING, SPECIAL	SQ YD	2150									2150	
* 25200200	SUPPLEMENTAL WATERING	UNIT	2112	2102								10 W	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1025	1025									
28000300	TEMPORARY DITCH CHECKS	EACH	65	65									
28000500	INLET AND PIPE PROTECTION	EACH	37	37									

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DUPAGE	563	5
STA.	TO STA.			
FED. ROAD T. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63024	

LEGEND:


- SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 1 OF 19

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN:	SHEET NO.
CHECKED:	
APPROVED:	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-7003 (985)