

SUMMARY OF QUANTITIES

| IDOT CODE NO. | PAY ITEM DESCRIPTION | UNIT | TOTAL | J000-2A | X928-2A | X071-2A | Y007 | Y031-1F | | | Y030-1E | Y060 | Y002 |
|---------------------|--|---------|-------|--|-------------------------------------|------------|--|----------------------|------------------------|-----------------------------------|----------|-------------------------|---------|
| | | | | ROADWAY | PEDSTRIAN TUNNEL & WEST WALLS | STRUCTURES | | TRAFFIC SIGNALS | | | LIGHTING | NAPERVILLE UTILITIES | SIGNING |
| | | | | 90% STATE, 10% DUPAGE COUNTY & NAPERVILLE | | BRIDGE | NORTHEAST & SOUTHEAST RETAINING WALLS | 75TH & WASHINGTON | WASHINGTON & HOBSON | TRAFFIC SIGNAL INTERCONNECT | | | |
| FUNDING | STP | STP/TCM | HBRRP | STP | STP | STP | STP | STP | STP | NON- PARTICIPATING | STP | | |
| 51603000 | DRILLED SHAFT IN SOIL | CU YD | 90 | | | 90 | | | | | | | |
| 51604000 | DRILLED SHAFT IN ROCK | CU YD | 101 | | | 101 | | | | | | | |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 295 | | | 295 | | | | | | | |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 43 | | | 43 | | | | | | | |
| 52100020 | ELASTOMERIC BEARING ASSEMBLY, TYPE II | EACH | 21 | | | 21 | | | | | | | |
| 52100520 | ANCHOR BOLTS, 1" | EACH | 128 | | | 128 | | | | | | | |
| 52100530 | ANCHOR BOLTS, 1 1/4" | EACH | 42 | | | 42 | | | | | | | |
| 54010603 | PRECAST CONCRETE BOX CULVERT, 6'X3' | FOOT | 380 | 380 | | | | | | | | | |
| 54207171 | PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND SIZE 36" | FOOT | 88 | 88 | | | | | | | | | |
| 54207183 | PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND SIZE 48" | FOOT | 330 | 330 | | | | | | | | | |
| 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | EACH | 4 | 4 | | | | | | | | | |
| 54213663 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" | EACH | 10 | 10 | | | | | | | | | |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | EACH | 3 | 3 | | | | | | | | | |
| 54213681 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36" | EACH | 2 | 2 | | | | | | | | | |
| 54213705 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60" | EACH | 1 | 1 | | | | | | | | | |
| 54214521 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND SIZE 36" | EACH | 2 | 2 | | | | | | | | | |
| 54214533 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND SIZE 48" | EACH | 2 | 2 | | | | | | | | | |
| 54215424 | CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24" | EACH | 1 | 1 | | | | | | | | | |
| 54215430 | CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30" | EACH | 1 | 1 | | | | | | | | | |
| 54215448 | CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48" | EACH | 1 | 1 | | | | | | | | | |
| 54244405 | FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 | EACH | 18 | 18 | | | | | | | | | |
| 542A0223 | PIPE CULVERTS, CLASS A, TYPE 1, 18" | FOOT | 113 | 113 | | | | | | | | | |
| 55035900 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 60, RISE 38 | FOOT | 333 | 333 | | | | | | | | | |
| 55037000 | STORM SEWERS, TYPE 3, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 60, RISE 38 | FOOT | 103 | 103 | | | | | | | | | |
| 550A0160 | STORM SEWERS, CLASS A, TYPE 1 36" | FOOT | 177 | 177 | | | | | | | | | |
| 550A0180 | STORM SEWERS, CLASS A, TYPE 1 42" | FOOT | 267 | 267 | | | | | | | | | |
| 550A0190 | STORM SEWERS, CLASS A, TYPE 1 48" | FOOT | 32 | 32 | | | | | | | | | |
| 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 6922 | 6922 | | | | | | | | | |
| 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | FOOT | 680 | 680 | | | | | | | | | |

| | | | | |
|---------------------|----------------|------------------|--------------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 2552 | 00-00114-00-PV | DUPAGE | 563 | 8 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | CONTRACT NO. 63024 | |

LEGEND:


- * SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 4 OF 19

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

| | |
|----------------------|------------------------------|
| DRAWN: | SHEET NO. |
| CHECKED: | |
| APPROVED: | |
| DATE: APRIL 11, 2008 | |
| SCALE: NONE | |
| JOB NO.: P-9I-494-00 | PROJECT NO.: M-CMM-7003 9851 |