

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DuPAGE	563	12
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 63024				

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1F			Y030-1E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE	STP/TCM	BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT	STP	NON-PARTICIPATING	STP
FUNDING	STP	HBRRP	STP	STP	STP	STP	STP	STP	STP	STP	STP		
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	199	199									
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1024	1024									
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	775	775									
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	69	69									
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	278	278									
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16									
78200420	GUARDRAIL MARKERS, TYPE B	EACH	15	15									
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5									
78300100	PAVEMENT MARKING REMOVAL	SQ FT	14448	14448									
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3							3			
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1							1			
81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	350		350								
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	3670					848	620	2202			
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	149					101	48				
81000800	CONDUIT IN TRENCH, 3" DIA., GLAVANIZED STEEL	FOOT	16					16					
81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GLAVANIZED STEEL	FOOT	13					13					
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	180						10	170			
81001100	CONDUIT IN TRENCH, 5", DIA., GALVANIZED STEEL	FOOT	112					112					
81001200	CONDUIT IN TRENCH, 6" DIA., GALVANIZED STEEL	FOOT	10					10					
81018200	CONDUIT PUSHED, 1" DIA., GALVANIZED STEEL	FOOT	560		560								
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	500							500			
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1554					163	358	1033			
81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	155					155					
81019100	CONDUIT PUSHED 6", GALVANIZED STEEL	FOOT	197					197					
81100100	CONDUIT ATTACHED TO STRUCTURE, 1/2" DIA., GALVANIZED STEEL	FOOT	290		290								
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	450		450								
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	2					2					
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	5		5								

LEGEND:


- SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 8 OF 19

TYLININTERNATIONAL

City of  **Naperville**

DRAWN: _____ SHEET NO. _____

CHECKED: _____

APPROVED: _____

DATE: APRIL 11, 2008

SCALE: NONE

JOB NO. P-91-494-00 PROJECT NO. M-CMM-7003 (1985)