

**SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DUPAGE	563	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 63024				

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X928-2A	X071-2A	Y007	Y031-1/F			Y030-1/E	Y060	Y002
				ROADWAY	PEDSTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE		BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT			
FUNDING	STP	STP/TCM	HBRRP	STP	STP	STP	STP	STP	STP	NON-PARTICIPATING	STP		
81302000	JUNCTION BOX, CAST IRON, ATTACHED TO STRUCTURE, 4" X 4" X 3"	EACH	3		3								
81400100	HANDHOLE	EACH	34					7	8	11	8		
81400200	HEAVY DUTY HANDHOLE	EACH	2					2					
81400300	DOUBLE HANDHOLE	EACH	6					5	1				
81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/2 NO. 10	FOOT	745		745								
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	15482					1060	678	2202	11542		
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	72								72		
82500505	LIGHTING CONTROLLER, SPECIAL	EACH	3								3		
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	3								3		
83007400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. MAST ARM	EACH	5								5		
83008400	LIGHT POLE, ALUMINUM, 40 FT. M.H., 10 FT. MAST ARM	EACH	62								62		
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	1065								1065		
83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	45								45		
83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	73								73		
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	26								26		
84200700	LIGHTING FOUNDATION REMOVAL	EACH	26								26		
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	13								13		
85700205	FULL ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1						1				
85700305	FULL ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1					1					
86000100	MASTER CONTROLLER	EACH	1					1					
86400100	TRANSCEIVER- FIBER OPTIC	EACH	2					1	1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	4652					3598	1054				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	7421					5192	2229				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2948					481	2467				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3546					2939	607				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	11415					8526	2889				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	124					72	52				
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1						1				
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1						1				

**LEGEND:**


- SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT  
WASHINGTON STREET - 75th STREET  
SUMMARY OF QUANTITIES

SHEET 9 OF 19

CONSULTANT  
**TYLIN INTERNATIONAL**

City of  **Naperville**

DRAWN: \_\_\_\_\_ SHEET NO. \_\_\_\_\_

CHECKED: \_\_\_\_\_

APPROVED: \_\_\_\_\_

DATE: APRIL 11, 2008

SCALE: NONE

JOB NO. P-91-494-00 PROJECT NO. M-CMM-7003 (985)